


# **Solid Waste Master Plan: 2006 Revision**

**June 2006**



**Commonwealth of Massachusetts  
Executive Office of Environmental Affairs  
Department of Environmental Protection**

## **EXECUTIVE SUMMARY**

The *2006 Plan Revision* updates the Commonwealth's policies and strategies for managing solid waste through 2010, to the extent that solid waste management is regulated or can be influenced by the Massachusetts Department of Environmental Protection (MassDEP) or Executive Office of Environmental Affairs (EOEA). This revision maintains the overall goals and strategies of the *Beyond 2000 Solid Waste Master Plan (Beyond 2000 Plan)*, while placing increased emphasis on expanding and targeting waste ban compliance and enforcement, leveraging resources and building partnerships, building cost-effective programs, and prioritizing materials and sectors where the greatest amount of waste reduction can be achieved.

Since the *Beyond 2000 Plan* was published in December 2000, (MassDEP), municipalities, citizens, businesses, and solid waste service providers have achieved significant accomplishments in reducing waste and furthering sustainable solid waste management, including:

- increasing Massachusetts' overall waste reduction rate from 53% in 1999 to 60% in 2004;
- reducing total disposal by 2% from 1999 to 2004, offsetting growing disposal rates during the 1990s;
- increasing the number of municipal Pay-As-You-Throw (PAYT) programs from 94 at the start of 2000 to 116 in 2004 and increasing the population served by PAYT programs by 30 percent;
- helping to establish a Supermarket Organics Recycling Network with nearly 60 participating stores, which have diverted between 60 and 75 percent of their waste and saved an average of \$45,000 per store; and
- promulgating revised Site Assignment regulations and revised Solid Waste Permitting regulations to improve facility operations and oversight.

At the same time, changes in the solid waste management landscape and in state and local government budgets have created a mix of new challenges and opportunities that have prompted MassDEP to review the goals, policies, and strategies of the *Beyond 2000 Plan*. The *2006 Plan Revision* addresses a number of key trends and challenges in solid waste management, including a changing fiscal climate, new projections for waste export, expansion of construction and demolition (C&D) processing capacity, strong recycling markets, and a new focus on public-private partnerships. To address these trends and challenges, MassDEP has developed a range of new and innovative waste reduction strategies, including expanding public-private partnerships, cost minimization tactics, and a combination of targeted grants and enforcement that will enable Massachusetts to continue to make progress towards our waste reduction goals.

## Waste Reduction Goals and Strategies

In the *Beyond 2000 Plan*, MassDEP established a vision to dispose of the “irreducible minimum” amount of waste through waste reduction efforts. MassDEP remains committed to the aggressive waste reduction goals established in the *Beyond 2000 Plan* and believes continued progress can be made in reducing waste by working in close partnership with a wide range of stakeholders. Therefore, MassDEP has maintained the 70 percent waste reduction goal by 2010 established in the *Beyond 2000 Plan*. MassDEP believes that a waste reduction goal that measures source reduction and recycling is a better measure than recycling alone; however, MassDEP has found that a recycling goal is simpler and easier to explain. Therefore, MassDEP also has established a recycling goal of 56 percent, eight percentage points above the 2004 recycling rate.

While MassDEP’s overall vision and goals for solid waste have not changed, MassDEP and other stakeholders recognize that, at least for the immediate future, current funding and staffing levels require new and innovative waste reduction strategies that build on the successful initiatives of the past five years. At the same time, strong recycling markets present new opportunities to advance recycling through innovative partnerships that can both increase diversion and save money. The *2006 Plan Revision* establishes strategies that recognize these opportunities and seek to increase enforcement of existing regulatory requirements, build new partnerships, leverage resources from a wide range of stakeholders, increase efficiency, and reduce costs for businesses and municipalities. These strategies will emphasize the following:

- **Expand and Target Compliance and Enforcement** – MassDEP will use focused compliance and enforcement tools to increase waste reduction, targeting its resources on expanded waste ban enforcement and ensuring solid waste facilities operate safely.
- **Leverage Resources/Build Partnerships** – MassDEP will establish agreements and partnerships for reducing waste with product manufacturers, retailers, trade associations, and cities and towns; leverage matching grant contributions; seek additional funding sources; and coordinate with other state initiatives that can increase waste reduction.
- **Build Cost-Effective Programs Based on Recycling Market Opportunities** – Strong recycling markets provide excellent opportunities to reduce waste cost-effectively. Due to rapidly growing international markets, scrap paper is now the number one American export by volume, and exports of U. S. scrap of all kinds grew to \$8.4 billion last year, more than double the 1999 total. This strong international demand has raised payments for recycled paper to between \$80 and \$120 per ton and has created a recycled paper supply shortage for American paper mills<sup>1</sup>. However, plenty of paper remains in the waste stream and, by not recycling, Massachusetts businesses and residents are literally throwing money away. An estimated 1.5 million tons of paper<sup>2</sup>, with an estimated value

---

<sup>1</sup> Industry News: U.S. Paper Recycling Reaches a Record High, Source: Knight Ridder Washington Bureau, February 9, 2005.

<sup>2</sup> Waste Reduction Program Assessment and Analysis for Massachusetts, Tellus Institute, December 2002.

of more than \$100 million<sup>3</sup>, is thrown away each year by Massachusetts residents and businesses. Similar market dynamics exist for other recyclable commodities. While recycling markets are cyclical and could decline in the future, generators that reduce the amount of waste disposed can still save money through avoided disposal fees, which are typically \$60-80 per ton in Massachusetts. MassDEP will provide hands-on technical assistance to municipalities and businesses that emphasizes waste reduction initiatives that save money such as Pay-As-You-Throw, improved recycling and solid waste contracting, increased participation in existing programs, and regional program coordination.

- **Focus On Priority Materials/Sectors** – In 2002, the Tellus Institute assessed potential additional waste reduction by waste sector and material category in Massachusetts, providing valuable guidance for targeting program efforts<sup>4</sup>. MassDEP will focus efforts on those waste streams with the greatest additional diversion potential and benefits, including:
  - **Commercial Municipal Solid Waste (MSW): organics (especially food waste) and paper and cardboard** – These materials have a combined additional annual waste reduction potential of more than 1.6 million tons, representing more than 75% of the total additional commercial waste reduction potential of 2.2 million tons per year. Both of these streams have the potential to be recycled or composted cost-effectively well beyond existing levels.
  - **Residential MSW: organics (leaves, yard waste and food waste) and paper (including cardboard)** – These materials have a combined additional annual waste reduction potential of more than 1.1 million tons, representing more than 75% of the total additional residential waste reduction potential of 1.5 million tons per year. Both of these streams, especially paper, have the potential to be recycled or composted cost-effectively well beyond existing levels.
  - **C&D: wood, asphalt shingles, and gypsum wallboard** – Wood and asphalt shingles represent the largest un-diverted portion of C&D waste, as asphalt, brick, and concrete (ABC) are recycled at a very high rate. Excluding ABC, remaining C&D materials are only recycled at a 10 percent rate. Recycling gypsum wallboard will reduce hydrogen sulfide odors at landfills and landfill closure projects<sup>5</sup>.

The *Beyond 2000 Plan* established a goal to “Substantially reduce the use and toxicity of hazardous products and provide convenient collection services to all residents and very small quantity hazardous waste generators.” MassDEP has had success in helping to clean out chemicals in schools and encourage increased collection of hazardous household products, but much remains to be done to reduce the toxicity of the waste stream. Reducing the toxicity of the waste stream poses different challenges than other waste reduction programs. Unlike recycling

---

<sup>3</sup> “It’s Time to Be Proactive: Let’s Use Our Regional Strengths”, presentation by Pete Grogan, Weyerhaeuser, NERC Fall Conference, October 27, 2004.

<sup>4</sup> Figures cited for additional diversion potential throughout this report are based on *Waste Reduction Program Assessment and Analysis for Massachusetts*, prepared for MassDEP in December 2002, by the Tellus Institute.

<sup>5</sup> Although wood, shingles, and wallboard will be targeted for increased diversion, much of the projected tonnage increase in C&D recycling is expected to come from recycling increased amounts of asphalt, brick, and concrete (ABC) due to increased generation of those materials.

programs, which have the potential to help cities and towns save money, running hazardous product collection programs typically costs cities and towns money and some towns have eliminated or reduced their hazardous products collection programs in recent years. While some manufacturers have taken steps to reduce the toxicity of their products or established limited collection programs, these initial efforts need to be encouraged.

MassDEP has maintained the toxicity reduction goal laid out in the *Beyond 2000 Plan* as a long-term goal. MassDEP's immediate priority is to help maintain existing local and regional hazardous product collection programs and facilities, while making further progress in specific target areas such as mercury-containing products. MassDEP will seek to maximize sharing of reciprocal collection program access among nearby municipalities through regional agreements. MassDEP also will partner with other state agencies and manufacturers to reduce the toxicity of products entering the waste stream through a combination of voluntary partnerships, education and, where possible, regulatory and statutory initiatives.

### **Waste Management Capacity**

In 2003, MassDEP changed the way it projects waste management capacity. Instead of showing a single set of values for projected in-state capacity and net export, MassDEP now projects a range based on two scenarios; one assuming the recycling rate would remain flat and the other assuming the recycling rate would grow to meet the 2010 milestone. These projections show projected net export of between 1.0 million and 2.1 million tons by 2010 and between 1.9 million and 3.0 million tons by 2012.

Massachusetts has sought to maintain enough solid waste management capacity to manage its own waste. However, due to various factors, including regional market conditions, Massachusetts has been a net exporter of waste for several years, and this trend is expected to continue.

In 2004, Massachusetts generated 13.9 million tons of waste, of which 12.4 million tons was managed through diversion (7.6 million tons) or in-state disposal (4.8 million tons), while 1.6 million tons was exported for disposal (on a net basis). Net export of waste represents final waste management capacity that is not available within Massachusetts.

The *Beyond 2000 Plan* established a policy goal of achieving no net import or export of solid waste by 2006. Under this policy, MassDEP would permit additional landfill disposal capacity up to, but not above, the amount of waste requiring disposal. Given planned landfill projects and projected recycling rates, it is clear that Massachusetts will not reach a no net import/export level in 2006. However, MassDEP believes that there are important benefits to striving towards a balanced waste management system, including cost savings from increased recycling, availability of local waste management options, and reduced reliance on fluctuating out-of-state disposal markets. Therefore, MassDEP will maintain a long-term goal of reaching no net import/export, but will not attach a milestone date to this goal. MassDEP will continue to assess and evaluate the Commonwealth's solid waste management needs, but will focus its resources on promoting waste reduction while relying on markets to ultimately guide disposal capacity decisions. MassDEP will place special emphasis on supporting the development of additional in-

state organics processing capacity, which can help businesses, cities and towns save money, reduce pressure on disposal capacity, create a valuable product, and support creation of additional jobs in Massachusetts.

Unless and until net export drops dramatically, MassDEP will no longer limit allocation of disposal capacity for new or expanded landfills. MassDEP will review all landfill proposals based solely on site assignment and permitting requirements.

MassDEP will maintain a moratorium on new municipal waste combustion capacity due to concerns about mercury emissions. Despite significant reductions in mercury emissions over the past several years, municipal waste combustion facilities continue to represent the largest in-state source of mercury emissions. MassDEP believes that further expanding municipal waste combustion capacity, which already represents nearly 50 percent of Massachusetts total disposal capacity and 65 percent of in-state disposal capacity, is inconsistent with EOEA's Zero Mercury Strategy and the New England Governors/Eastern Canadian Premiers Mercury Strategy.

### **Facility Oversight**

Since the *Beyond 2000 Plan* was issued, MassDEP promulgated major revisions to the Site Assignment regulations (310 CMR 16.000) and the Solid Waste Facility Permitting regulations (310 CMR 19.000). MassDEP also has developed several guidance documents supporting these regulatory changes. These regulatory and policy initiatives maintain the policy framework established in the *Beyond 2000 Plan*.

MassDEP is continuing to develop approaches to effectively oversee solid waste facilities and materials management including:

- Developing guidance on addressing hydrogen sulfide emissions from landfills. MassDEP expects to complete this guidance in 2006.
- Improving oversight and tracking of landfill gas emissions from both active and inactive landfills.
- Ensuring waste ban compliance by waste haulers and generators, along with solid waste facilities.
- Implementing a policy signed in 2005 that eases the collection of sharps from home health care uses out of the recycling and trash streams

## 1. INTRODUCTION

### 2006 Solid Waste Master Plan Revisions

In December 2000, the Massachusetts Department of Environmental Protection (MassDEP) published the *Beyond 2000 Solid Waste Master Plan (Beyond 2000 Plan.)* To the extent that solid waste management is regulated or can be influenced by MassDEP and EOE, this plan established a long-term vision, as well as specific policies and strategies, for how to manage the Commonwealth's solid waste from 2000 through 2010.

MassDEP committed to reviewing the *Beyond 2000 Plan* after several years of implementation and updating it as needed. MassDEP conducted this review in late 2004 / early 2005 and held several meetings with the Solid Waste Advisory Committee<sup>6</sup> and consulted with other interested stakeholders. This review affirmed the overall goals and framework of the *Beyond 2000 Plan*, but recognized that changes in the waste management system (including stagnant recycling rates, decreasing in-state disposal capacity, and cuts in state funding for waste reduction programs) as well as new waste reduction strategies and opportunities required revisions to the Plan to re-focus strategies for achieving the Plan's goal of 70% waste reduction by 2010. The *2006 Plan Revision* updates the strategies in the *Beyond 2000 Plan* to adjust to these recent changes and to take advantage of new opportunities and strategies.

In September 2005, MassDEP issued the Draft Solid Waste Master Plan Revision, held four public hearings, and accepted public comment until November 4, 2005. MassDEP made a number of revisions in the final *2006 Plan Revision* in response to public comments and prepared a Response to Comments document. Changes made in response to comments include refining and expanding initiatives to improve C&D materials management and updating program descriptions and recommendations. MassDEP also included new 2004 solid waste data in the final *2006 Plan Revision* and updated waste management capacity projections based on the 2004 data.

### Background

Since the *Beyond 2000 Plan* was published, MassDEP, municipalities, citizens, businesses, and solid waste service providers achieved significant accomplishments in reducing waste and furthering sustainable solid waste management. Highlights of these accomplishments are found in three Progress Reports on the *Beyond 2000 Solid Waste Master Plan*, available on MassDEP's website at [www.mass.gov/dep](http://www.mass.gov/dep). From 1999 through 2004:

- Waste reduction (which is a measure of source reduction plus recycling) increased from 53 percent to 60 percent from 1999 to 2004<sup>7</sup>.
- Recycling rates kept pace with an 11 percent increase in generation over this five-year period, at 35 percent for MSW and 71 percent for C&D in 2004.

---

<sup>6</sup> Solid Waste Advisory Committee members are listed on DEP's website at [www.mass.gov/dep](http://www.mass.gov/dep)

<sup>7</sup> The originally published waste reduction rate for 1999 was 51%; however, this rate has been updated based on updated Gross State Product data that is used to calculate the waste reduction rate.

## Solid Waste Master Plan: 2006 Plan Revision

- Total disposal dropped 2 percent from 1999 to 2004, from 6.5 million to 6.4 million tons.
- Net export for disposal has continued at about 1.5 million tons per year.

The *2006 Plan Revision* addresses a number of key trends in solid waste management:

**Waste Export:** Net export of waste for disposal is projected to continue throughout the remainder of this decade as in-state landfills fill up and limited new capacity comes on-line. Depending on recycling progress, net export is projected to be between 1.0 and 2.1 million tons by 2010 and between 1.9 and 3.0 million tons by 2012. As a result, Massachusetts will need to rely on the export of solid waste to meet its waste management needs.

**Changes in Fiscal Conditions:** Over the past several years, changing fiscal conditions in both state and municipal budgets have necessitated difficult budget cuts throughout state and local governments. Along with many other programs, recycling programs have seen their funding reduced, primarily in the area of municipal grants. The *2006 Plan Revision* includes a range of new and innovative strategies that target existing resources more effectively and leverage other resources wherever possible. MassDEP believes that these strategies will enable Massachusetts to continue to make progress towards these waste reduction goals.

**C&D Processing Growth:** Over the past five years, seven new construction and demolition (C&D) processing facilities have been built, adding approximately 800,000 tons of annual processing capacity in Massachusetts. Most of the material produced by these facilities is used at active and inactive landfills as daily cover and shaping and grading material. Although this use has helped to properly close and cap old unlined landfills, it also has resulted in odor and operational problems in a number of cases. MassDEP will focus on improving management of these materials while continuing to develop improved C&D end markets that are less dependent on landfills.

**Organics Diversion Opportunities:** Diversion of organics (e.g., food waste) has grown over the past several years and shows significant future potential. This growth is limited by a lack of in-state organics processing capacity, with a projected need of more than 380,000 tons per year by 2010 versus current permitted annual capacity of 130,000 tons. Because it is not cost-effective to transport food waste long distances, it will become increasingly important to develop local processing capacity to support increased diversion from large generators.

**Strong Recycling Markets:** Strong national and international markets for paper and other recyclables have created a supply shortage for paper mills and other companies that use recyclable commodities, increasing the value of recyclables. Because of the strong long-term outlook for recycling markets combined with opportunities to lower disposal costs, which are typically \$60-80 per ton in Massachusetts, many cities and towns and businesses can divert more materials and reduce their costs if they implement recycling programs efficiently.

### Summary

MassDEP is committed to the aggressive waste reduction goals established in the *Beyond 2000 Plan* and believes continued progress can be made in reducing waste by working in close



## Solid Waste Master Plan: 2006 Plan Revision

partnership with a wide range of stakeholders. While MassDEP's overall vision and goals for solid waste have not changed, MassDEP and other stakeholders recognize that, at least for the immediate future, current funding and staffing levels require new waste reduction strategies that are less dependent on state funding. At the same time, strong recycling markets present new opportunities to advance recycling through innovative and efficient partnerships that can both increase diversion and save money. The *2006 Plan Revision* establishes strategies that recognize these trends and seek to increase enforcement of existing regulatory requirements, build new partnerships, leverage resources from a wide range of stakeholders, increase efficiency, and reduce costs for businesses and municipalities.

## **2. WASTE REDUCTION STRATEGY**

### **2010 Waste Reduction and Recycling Rate Goals**

MassDEP believes it is important to maintain an aggressive waste reduction goal to provide a clear focus for the Commonwealth's waste reduction strategies. Therefore, DEP has maintained the 70 percent waste reduction goal by 2010 established in the *Beyond 2000 Plan*.

MassDEP believes that a waste reduction goal that measures source reduction and recycling is a better measure than recycling alone; however, MassDEP has found that a recycling goal is simpler and easier to explain. Therefore, MassDEP has established a recycling sub-goal of 56 percent. MassDEP estimates that a 56 percent overall recycling rate, combined with expected source reduction, will meet the 70 percent waste reduction goal. MassDEP estimates that solid waste generation will be approximately 15.7 million tons in 2010. A 56 percent recycling goal would require 8.7 million tons of recycling in 2010, approximately 2.0 million tons more than the 6.7 million tons recycled in 2004.

### **2010 Toxicity Reduction Goals and Strategies**

The *Beyond 2000 Plan* established a goal to "Substantially reduce the use and toxicity of hazardous products and provide convenient collection services to all residents and very small quantity hazardous waste generators." MassDEP has had success in helping to clean out chemicals in schools and encourage increased collection of hazardous household products, but much remains to be done to reduce the toxicity of the waste stream. Reducing the toxicity of the waste stream poses different challenges than other waste reduction programs. Unlike recycling programs, which have the potential to help cities and towns save money, running hazardous product collection programs typically costs cities and towns money and some towns have eliminated or reduced their hazardous products collection programs in recent years. Some manufacturers have taken steps to reduce the toxicity of their products or established limited collection programs, such as reducing lead in electronics and coated wire uses and holding pilot electronics collection events. These initial efforts need to be encouraged.

MassDEP will maintain the toxicity reduction goal laid out in the *Beyond 2000 Plan* as a long-term goal. Currently, an estimated 65 percent of residents live in communities with access to comprehensive, convenient programs, while other residents have access to somewhat less convenient collection opportunities. MassDEP's short-term priority is to help maintain existing local and regional hazardous product collection programs and facilities, while making further progress in specific target areas such as mercury containing products. MassDEP will seek to maximize sharing of reciprocal collection program access among nearby municipalities through regional agreements. MassDEP also will partner with other state agencies and manufacturers to reduce the toxicity of products entering the waste stream through a combination of voluntary partnerships and education.

## Key Waste Reduction Strategies

MassDEP recognizes that different waste reduction strategies are necessary to respond to the challenges and opportunities presented by current trends in solid waste management. These strategies will emphasize the following:

- **Expand and Target Compliance and Enforcement** – MassDEP will use focused compliance and enforcement tools to increase waste reduction, by targeting its resources on waste ban enforcement and ensuring solid waste facilities operate safely.
- **Leverage Resources/Build Partnerships** – MassDEP will establish agreements and partnerships for reducing waste with product manufacturers, retailers, trade associations, and cities and towns; leverage matching grant contributions; seek additional funding sources; and coordinate with other state initiatives that can increase waste reduction.
- **Build Cost-Effective Programs Based on Recycling Market Opportunities** – Strong recycling markets provide excellent opportunities to reduce waste cost-effectively. Due to rapidly growing international markets, scrap paper is now the number one American export by volume, and exports of U.S. scrap of all kinds grew to \$8.4 billion last year, more than double the 1999 total. This strong international demand has raised payments for recycled paper between \$80 and \$120 per ton and created a recycled paper supply shortage for American paper mills<sup>8</sup>. However, plenty of paper remains in the waste stream and, by not recycling, Massachusetts businesses and residents are literally throwing money away. An estimated 1.5 million tons of paper<sup>9</sup>, with an estimated value of more than \$100 million<sup>10</sup>, is thrown away each year by Massachusetts residents and businesses. Similar market dynamics exist for other recyclable commodities. While recycling markets are cyclical and could decline in the future, generators can still save money through recycling, composting, and reducing waste through avoided disposal fees, which are typically \$60-80 per ton in Massachusetts, if not higher. MassDEP will provide hands-on technical assistance to municipalities and businesses that emphasizes waste reduction initiatives that save money such as Pay-As-You-Throw, improved recycling and solid waste contracting, increased participation in existing programs, and regional program coordination.
- **Focus On Priority Materials/Sectors** – In 2002, the Tellus Institute assessed potential additional waste reduction by waste sector and material category in Massachusetts, providing valuable guidance for targeting program efforts. MassDEP will focus efforts on waste streams with the greatest additional diversion potential and benefits, including:
  - **Commercial Municipal Solid Waste (MSW): organics (especially food waste) paper, and cardboard** – These materials have a combined additional annual waste

---

<sup>8</sup> Industry News: U.S. Paper Recycling Reaches a Record High, Source: Knight Ridder Washington Bureau, February 09, 2005.

<sup>9</sup> Waste Reduction Program Assessment and Analysis for Massachusetts, Tellus Institute, December 2002.

<sup>10</sup> “It’s Time to Be Proactive: Let’s Use Our Regional Strengths”, presentation by Pete Grogan, Weyerhaeuser, NERC Fall Conference, October 27, 2004.

reduction potential of more than 1.6 million tons<sup>11</sup>, representing more than 75 % of the total additional commercial waste reduction potential of 2.2 million tons per year. Both of these streams have the potential to be recycled or composted cost-effectively well beyond existing levels.

- **Residential MSW: organics (leaves, yard waste and food waste) and paper (including cardboard)** – These materials have a combined additional annual waste reduction potential of more than 1.1 million tons, representing more than 75 % of the total additional residential waste reduction potential of 1.5 million tons per year. Both of these streams, especially paper, have the potential to be recycled or composted cost-effectively well beyond existing levels.
- **C&D: wood, asphalt shingles, and gypsum wallboard** – Wood and asphalt shingles represent the largest un-diverted portion of C&D waste, as asphalt, brick, and concrete (ABC) are recycled at a very high rate. Excluding ABC, remaining C&D materials are only recycled at a 10 percent rate. Therefore, MassDEP's efforts will focus on these other materials, particularly wood, gypsum wallboard, and asphalt shingles. Improving management of gypsum wallboard is a priority as gypsum has been identified as the primary factor causing hydrogen sulfide generation from C&D fines and residuals used for landfill daily cover and as grading and shaping material at landfill closure projects<sup>12</sup>.

Throughout the remainder of this section, strategies for each program area are grouped in three categories:

- **New:** Initiatives that were not included in the *Beyond 2000 Plan*. In some cases, these initiatives are entirely new; in other cases, they began within the past several years.
- **Revised/Expanded:** Initiatives that have been or are being significantly changed since the *Beyond 2000 Plan*.
- **Continued:** Initiatives in the *Beyond 2000 Plan* that MassDEP is maintaining as they are.

### Commercial Waste Reduction Strategy

MassDEP will focus its commercial waste reduction programs on increasing diversion of paper and organic wastes – especially food waste. MassDEP estimates that more than 1.6 million additional tons of these materials could be cost-effectively diverted from disposal annually by 2010. This increased diversion will require a combination of strong partnerships and new enforcement strategies to be effective. Strategies by material category are summarized below, followed by a description of each of the specific elements of MassDEP's commercial waste reduction strategy.

**Paper:** Paper materials make up nearly 40 percent of commercial waste disposal, and even more of potential additional commercial waste reduction. A strong regional, national, and international recycling infrastructure is already in place for paper. Increased amounts of post-

---

<sup>11</sup> Additional waste reduction potential includes recycling, composting, and source reduction.

<sup>12</sup> Although wood, shingles, and wallboard will be targeted for increased diversion, much of the projected tonnage increase in C&D recycling is expected to come from recycling increased amounts of asphalt, brick and concrete (ABC) due to increased generation of those materials.

consumer paper and cardboard are needed to meet increasing levels of industry demand. As a result, markets for all grades of paper have a very strong long-term outlook. MassDEP believes that Massachusetts businesses and institutions, especially small to medium-sized businesses, can significantly increase paper recycling, and that a mix of assistance, partnerships, and enforcement can help spur on this increased recycling, save businesses money, and support Massachusetts' paper recycling and manufacturing industries.

**Food Waste and Other Organics:** Food waste and other organics make up nearly 30 percent of commercial waste disposal, and even more of potential additional commercial waste reduction. The picture for food waste is much different than paper. Massachusetts has a limited infrastructure for hauling and processing food waste. MassDEP estimates that more than 1.1 million tons of commercial and institutional food waste will be generated annually in Massachusetts by 2010, with less than 10 percent currently diverted. MassDEP believes that Massachusetts can achieve a 34 percent diversion rate for this material, or 380,000 tons per year, by 2010. However, only 130,000 tons of annual food waste processing capacity is currently permitted in Massachusetts, leaving a gap of at least 250,000 tons statewide. Establishing in-state food waste processing capacity is critical because this material cannot be cost-effectively transported long distances. Like most solid waste management capacity, food waste processing capacity has been difficult to site due in large part to objections from communities about potential traffic, noise, and odor impacts.

MassDEP's strategy for increasing food waste diversion will focus on simultaneously building the Commonwealth's processing and hauling infrastructure and working with targeted groups of commercial and institutional generators that generate the most food waste and have the best opportunity to cost-effectively divert food waste from disposal. These sectors include supermarkets, hospitals and other health care facilities, hotels and convention centers, colleges and universities, and state institutions such as prisons.

## **Commercial Waste Reduction Initiatives**

### **NEW**

- **Enforce Waste Bans Comprehensively and Equitably:** MassDEP will ensure that waste haulers and generators, as well as solid waste facilities, are in compliance with the waste bans. Under the waste ban regulations, no person is allowed to dispose or contract for disposal of restricted materials. Along with solid waste facilities, waste haulers and generators have a shared responsibility to comply with waste bans and avoid the disposal of restricted materials. MassDEP plans to continue to conduct waste ban inspections at solid waste facilities. Now these inspections will also evaluate whether waste haulers and generators are bringing in banned materials for disposal. When haulers and generators of failed loads can be identified, MassDEP will pursue enforcement against those entities. Although MassDEP does not expect to conduct waste ban inspections at generator or hauler locations at this time, MassDEP may choose to evaluate compliance at these locations in the future.

- **Expand Organics Processing Capacity:** Work with farms, cities, and towns and large institutions to expand organics processing capacity in Massachusetts, including:
  - Work with interested cities and towns with well-run composting operations to expand those sites to accept food waste from local food waste generators, and
  - Work with large institutions to develop increased on-site composting capacity. MassDEP will work closely with existing and new facility operators through a combination of outreach and technical assistance to expand organics processing capacity and ensure that composting operations are well run and do not create odor or other nuisance concerns.
- **WasteWise Partnership with EPA:** MassDEP recently established the first state WasteWise partnership with EPA, leveraging additional resources to support and recognize Massachusetts business and institutional recycling programs. This WasteWise Partnership will be used to support MassDEP's other targeted initiatives to increase commercial waste reduction, especially for medium and large businesses. As with other commercial waste reduction efforts, MassDEP will consider emphasizing those business sectors with the greatest additional diversion potential.
- **Continue Resource Management Contracting:** MassDEP will continue to support the development of Resource Management (RM) Contracting models for businesses and institutions. Through RM contracting, both the generator and the hauler share incentives for reducing waste, increasing recycling, and saving money. A recent one-year pilot project at Shattuck Hospital was successful in saving \$11,000 annually by reducing disposal by 11 percent and more than tripling recycling and other diversion.
- **Surplus Office Equipment Reuse:** MassDEP will continue to work with the state's Operational Services Division, other state agencies, cities and towns, and other institutions to arrange exchanges of surplus office equipment, saving money for both parties while avoiding sending surplus, still usable office equipment for disposal. This will include developing a user-friendly website for state agencies and others seeking surplus equipment.

REVISED/EXPANDED

- **Expand Supermarket Partnership:** MassDEP will continue an innovative partnership with major supermarket chains, the Massachusetts Food Association (MFA), and haulers and compost facilities to increase supermarket composting and recycling. Major elements of this partnership include:
  - A memorandum of understanding (MOU) between MassDEP, the MFA, and major supermarket chains to establish program and performance standards for supermarket recycling and composting programs. This MOU exempts participating supermarkets from waste ban inspections, similar to exemptions for municipalities with Department Approved Recycling Program (DARP) status.
  - Hands-on technical assistance to supermarkets from leading industry consultants to help them establish and maintain effective diversion programs.

**Build Other Business Partnerships:** MassDEP will seek to develop similar partnerships with other business sectors that have high levels of potential additional diversion. Hospitals and other health care service providers are strong candidates since they dispose of large amounts of paper in particular<sup>13</sup>. MassDEP has joined Hospitals for a Healthy Environment (H2E) as a “Champion for Change”. MassDEP will work in partnership with H2E as well as the Massachusetts Hospital Association on promoting waste and toxicity reduction. MassDEP will provide technical assistance to hospitals and other healthcare facilities to implement expanded waste reduction programs.

#### CONTINUED

- **Continue Facility Waste Ban Enforcement:** MassDEP will continue to maintain a presence at solid waste facilities to ensure that they are properly implementing their waste ban compliance plans. MassDEP will check waste ban compliance as a routine part of all solid waste facility inspections and also will conduct targeted waste ban enforcement initiatives.
- **Explore Waste Ban for Commercial Food Waste:** As stated in the *Beyond 2000 Plan*, MassDEP will continue to consider adding commercial and institutional food waste as an item banned from disposal. As with other waste bans, this will be dependent on sufficient infrastructure being developed to handle commercial and institutional food waste. An extension of the waste bans to commercial food waste would require a regulatory change with public hearing and comment.
- **Support Municipal Recycling Programs for Small Businesses:** MassDEP recently worked with the Northeast Recycling Council (NERC) to establish a statewide database of business recycling programs sponsored or operated by municipalities. MassDEP’s regional Municipal Assistance Coordinators will use this resource to support the development of new and expanded small business recycling programs in interested municipalities. Depending on contracting arrangements, cities and towns may be able to obtain revenue while reducing costs for their small businesses.
- **Recycling Market Development Assistance:** MassDEP’s funding for recycling market development grant programs has been cut dramatically. In addition, the Chelsea Center for Recycling and Economic Development, which had provided assistance, resources, and funding to support companies that use recycled products, has closed. MassDEP remains committed to fostering recycling markets through a combination of awarding limited, targeted grants, building industry partnerships, and providing information and referrals to companies interested in using recycled feed-stocks to produce new products. Specific initiatives include:
  - Provide limited Recycling Industry Reimbursement Credit grants to support the use of target recyclable materials as feed-stocks for manufacturing processes. Target materials include organics and C&D materials.

---

<sup>13</sup> According to DEP’s Commercial Waste Disposal Assessment published in 2000, the medical and health services sector disposes of more paper than any other single business sector in Massachusetts – 220,000 tons per year.

- Provide low-interest loans from the Recycling Loan Fund, currently capitalized at \$3.1 million, to enable recycling processors and manufacturers to obtain conventional financing to support facility expansions and development of new facilities.
  - Refer interested businesses to market development assistance, resources, and information available on MassDEP's market development web page and through other agencies.
  - Work with the Executive Office of Environmental Affairs and the Operational Services Division to establish recycled product purchasing mandates for state agencies, with an emphasis on compost and construction materials.
- **Business Outreach and Information:** MassDEP will rely on partnerships with WasteCap and the Earth's 911 recycling web site to provide recycling and composting information to businesses.

### **Residential Waste Reduction Strategy**

Ninety percent of Massachusetts residents have access to convenient recycling collection programs. Due to strong recycling markets, MassDEP sees promising opportunities to work with cities and towns to capture significantly more material from existing recycling programs and to do so in a way that will make these programs more efficient and save municipalities money.

MassDEP's work to advance residential waste reduction will achieve the greatest tonnage increases from paper (all types of paper, including cardboard) and organics (yard waste and food waste). Together, these material categories represent more than 1.1 million tons of additional diversion potential, more than 75 percent of the additional diversion potential for residential waste. The strategies for these materials are summarized below, followed by a description of each of the elements of MassDEP's residential waste reduction strategy.

**Paper:** Massachusetts has a mature paper recycling infrastructure. International demand for waste paper is very strong and is expected to remain so for some time, driving up payments for paper recycling. These high paper values provide a powerful financial incentive for municipalities to increase paper recycling by increasing participation rates in existing programs. Such initiatives also will typically increase recycling of other materials in addition to paper, such as food and beverage containers. In addition to supporting increasing participation in existing programs, MassDEP will devote some resources to help municipalities maintain current recycling services and avoid backsliding and to expand programs to collect all types of paper for recycling. Because of the promising long-term market outlook for paper and other recyclables, MassDEP believes that increasing paper recycling (as well as recycling of many other materials) will be cost-effective for most municipal recycling programs.

**Yard and Food Waste:** Strategies to increase diversion of yard waste, either through home or municipal composting programs, will be similar to those for paper. In some cities and towns, there is a greater need to expand yard and food waste composting programs to make them more convenient for residents. In most cases, municipalities have established yard waste composting



programs, and the greatest increases will come from expanding collection services or increasing home composting bin distribution.

Residential food waste composting is not widely established and is primarily limited to home composting. While residential food waste could potentially be captured through programs that collect yard waste, Massachusetts' food waste processing infrastructure must become better established before widespread residential food waste collection programs can occur. MassDEP is seeking to make food waste collection and composting more cost effective by working with commercial and institutional food waste generators, haulers, and composting facilities to expand locally available composting infrastructure. Once this collection and processing system has become better established for commercial and institutional generators and made more efficient, MassDEP will work more closely with municipalities to develop residential food waste composting programs.

### **Residential Waste Reduction Initiatives**

#### **NEW**

- **Municipal Recycling Savings Program:** MassDEP will conduct outreach to municipal officials and residents to highlight the cost savings opportunities from strong recycling markets. MassDEP will continue to provide municipalities with a combination of hands-on assistance, targeted grants and information to help them develop and implement recommended program options such as Pay-As-You-Throw, recycling set-out requirements, outreach and incentives, and improved contracting to maximize capture of recyclables and save money.
- **Pilot Municipal Collection and Efficiency Improvements:** MassDEP will work with interested cities and towns to pilot new strategies to increase capture rates and collection efficiencies of recycling collection programs, including providing larger or second bins, establishing targeted incentive programs, and exploring approaches for implementing local recycling requirements.
- **Support Municipal Mandatory Recycling Initiatives:** MassDEP will work with cities and towns that choose to establish mandatory recycling initiatives at the local level. Cities and towns have found that these initiatives are effective at increasing recycling and reducing disposal, thereby saving municipalities money. When supported by extensive outreach, these initiatives have been very effective. MassDEP's role will include supporting case studies and pilot projects, providing guidance and model requirements, and encouraging mandatory recycling through revised Department Approved Recycling Program (DARP) standards.
- **School Green Team:** MassDEP sponsors a school educational program called the Green Team, which provides fun and interactive ways for students and teachers to learn how to reduce, reuse, recycle and compost in their classrooms, schools, homes and communities. Participating classes receive educational materials, Certificates of Recognition and prizes.

Recycling equipment and a lending library of videos and curricula are also available to members.

- **Pilot Municipal Collection Improvements:** MassDEP will support pilot municipal programs to assess how new containers, equipment, and collection systems can increase diversion, particularly of paper, from existing programs.

#### REVISED/EXPANDED

- **Expand Pay-As-You-Throw:** At the end of 2004, 117 municipalities had adopted Pay-As-You-Throw (PAYT) programs, serving a population of about 1.3 million (about 20 percent of the state's population). MassDEP's goal is to expand PAYT programs so that more than 50 percent of Massachusetts residents will live in a community served by PAYT by 2010. To meet this goal, MassDEP will prioritize PAYT assistance to larger communities. Specific initiatives include:
  - Keep PAYT programs as MassDEP's top priority for limited municipal grants and technical assistance from MassDEP staff and regional assistance coordinators. MassDEP has dramatically increased this hands-on assistance over the past several years and will continue to do so.
  - Enhance PAYT outreach through MassDEP's web page, workshops for targeted audiences and geographic regions, coordination with the United States Environmental Protection Agency (U.S. EPA) Region 1, and outreach and assistance to individual municipalities and staff.
- **Regional Program Coordination and Technical Assistance:** MassDEP staff and the six regional Municipal Assistance Coordinators funded by MassDEP will continue to provide extensive hands-on assistance to cities and towns to improve their existing recycling and composting programs. This technical assistance is one of MassDEP's best tools for increasing residential waste reduction. The municipal coordinators will bring together groups of municipalities to develop cost-effective regional program solutions, as well as work with individual towns to improve their programs. Specific areas of emphasis will include:
  - Develop and implement PAYT programs.
  - Support development of more cost-effective regional contracts and service agreements for solid waste and recycling collection and processing, yard waste and brush grinding, hazardous products collection, and purchasing of recycling equipment; help municipalities increase their purchasing power and deliver services more cost-effectively.
  - Provide model recycling and trash service RFPs, recycling and hauler ordinances, and contracting assistance to enable municipalities to develop more effective recycling and trash contracts, which are critical for municipalities to be able to save money from increased recycling and composting.
  - Support local education and outreach initiatives to increase recycling participation.

## Solid Waste Master Plan: 2006 Plan Revision

- Consider funding other innovative technical assistance project requests, such as local zero waste projects.
- **Review Department Approved Recycling Program (DARP) Certifications:** MassDEP will review municipal DARP certifications to ensure that the incentives provided through DARP are working effectively. Particular focus will be placed on yard waste collection and composting programs.
- **Advance DARP Standards:** MassDEP extended the existing DARP recycling program standards through June 2006 to be consistent with the municipal fiscal year budget cycle, and issued new standards in January 2006 that will take effect in July 2006. Under DARP, participating municipalities that meet minimum recycling and composting criteria are exempt from waste ban inspections at disposal and transfer facilities. MassDEP has focused on criteria such as increasing the range of materials collected, PAYT, mandatory recycling, and other aggressive recycling participation programs that will increase diversion from existing programs and reduce disposal costs.
- **Springfield Materials Recycling Facility (MRF) Contract:** MassDEP has awarded a 10-year contract to Recycle America Alliance to operate the Springfield MRF (2005-2015, with a 5 year extension option). The contract was awarded through a competitive bid and provides approximately 90 contract municipalities with guaranteed recycling revenue of \$15.67 per ton of recyclables delivered, and an additional share of material revenues when the index price of recyclables exceeds \$40 per ton. MassDEP will continue to manage the operator's contract but has transferred responsibility for operating the weigh scales and maintaining the facility to the operator, thereby lowering MassDEP's costs.

### CONTINUED

- **Recycling and Composting Equipment and Education:** In addition to PAYT, education and outreach are important to maintain and increase participation in recycling and composting programs. Wherever possible these efforts will be focused on priority material categories. Specific initiatives include:
  - Provide grants for educational materials and technical assistance, targeting these to municipalities with new PAYT programs and other municipalities making significant program changes.
  - Maintain state contracts for recycling, composting, and hazardous products materials, equipment, and services. Municipalities rely on these contracts as an efficient means of procuring needed equipment and services without having to go out to bid.
  - Reduce the cost of municipal grants for customized recycling education materials by reducing the size of mailers and exploring other options to reduce the cost of printing and mailing this information.

## Solid Waste Master Plan: 2006 Plan Revision

- Produce generic press releases for local use and disseminate through the regional Municipal Assistance Coordinators.
  - Support the Earth's 911 web site to provide free local recycling information via the web.
  - Partner with other state and regional solid waste and recycling associations such as MassRecycle, the Massachusetts Chapter of the Solid Waste Association of North America, the National Solid Waste Management Association, the Construction Materials Recycling Association, and the Northeast Resource Recycling Association to hold jointly-sponsored workshops and conferences.
  - Solicit sponsors to offset the direct costs of workshops and conferences for municipal officials and recycling stakeholders.
- **Home Composting Programs:** Home composting programs save municipalities money by reducing the amount of trash they need to collect and dispose, and benefit residents who can produce compost for use on their lawns and gardens. MassDEP will continue to promote home composting through:
  - Home composting and healthy lawn and landscape workshops.
  - Targeted grants for home compost bins and kitchen food waste collection buckets.
  - Home composting exhibits and demonstrations at conferences, public events, and horticultural shows.
  - Distributing home composting literature, videos, and press releases to raise awareness of the benefits of home composting and how to compost.
- **Recycling Market Development/Product Stewardship:** The recycling market development strategies described above under the commercial waste reduction strategy will also support market development for priority residential wastestreams. Product stewardship approaches that increasingly involve manufacturers and retailers in managing products such as electronics after use can reduce recycling and disposal costs for cities and towns for these materials.
- **State and Municipal Purchasing Programs:** MassDEP will continue to work with the Operational Services Division and other state agencies to support State Sustainability initiatives for state agencies and provide cost-effective opportunities for municipalities and state agencies to buy recycled and environmentally preferable products. MassDEP will support recycled purchasing mandates for EOEA agencies, especially for compost and construction materials.
- **Expanded Bottle Bill:** MassDEP will continue to support passage of an expanded bottle bill to increase recycling of single-serve juice and water and other similar containers that are frequently consumed away from the home. MassDEP will seek to expand recycling programs at large public events and frequently used public venues, which would work well with an expanded bottle bill system.
- **Bottle Bill Administration:** MassDEP will continue to oversee ongoing coordination of the Commonwealth's bottle deposit law, including:

- Assisting EOEA with bottle bill policy and regulatory development.
  - Handling questions and complaints from consumers, redemption centers, distributors, and retailers regarding bottle bill issues.
  - Overseeing redemption center registrations.
  - Tightening bottle bill enforcement against fraudulent redemption.
  - Awarding redemption center grants.
- **Electronics Infrastructure and Regional Programs:** Over the past five years, MassDEP has worked with municipalities to establish an extensive collection system for computer monitors that contain cathode ray tubes, as well as televisions and other computer equipment. That system serves most residents in Massachusetts and has received national recognition. MassDEP will continue to provide information and technical assistance to support these efforts, while supporting regional and legislative initiatives to improve electronics collection and recycling programs.

### **Construction and Demolition Debris Waste Reduction Strategy**

The C&D recycling rate is already very high (71 percent in 2004), primarily because asphalt, brick, and concrete (ABC), which make up the bulk of C&D tonnage, is recycled at a very high rate. However, other C&D materials such as wood, asphalt shingles, and wallboard are only recycled at about a 17 percent rate.

Materials produced by C&D processors are primarily reused at landfills as fines for daily cover and residuals for grading and shaping purposes. These are relatively low value uses and have resulted in odor problems at a number of facilities, and also rely on landfill operations that are continually declining in Massachusetts. In the short term, MassDEP will work with C&D processors and landfill operators to improve the management of C&D fines and residuals at active and inactive landfills. At the same time and continuing in the long term, MassDEP will continue to stimulate additional market development to stimulate additional markets and uses for C&D materials that are not dependent on landfills. Fortunately, most C&D is generated by a relatively small group of companies, which makes it easier for MassDEP to target waste reduction initiatives. The strategies for reducing these material categories are summarized below, followed by a description of each of the elements of MassDEP's C&D waste reduction strategy.

**Wood:** MassDEP's strategy for increasing diversion of wood from disposal is centered on a disposal ban on wood, combined with technical assistance and partnerships to stimulate market development. The ban will take effect in July 2006 and has already stimulated C&D processing investments in Massachusetts. MassDEP will work with solid waste facilities to implement the ban and with the construction and demolition industry and other stakeholders to develop additional markets for C&D wood, particularly clean wood that can be separated at construction sites. MassDEP has approved Beneficial Use Determinations (BUDs) for materials that contain C&D wood, which may contain treated wood. These BUDs are for use of C&D fines as daily cover material and C&D residuals as grading and shaping material at landfills. The sampling and analytical requirements for these C&D fines and residuals include:

- Total RCRA 8 metals;
- Total petroleum hydrocarbons;
- Semi-volatile organic compounds;
- Volatile organic compounds;
- Loss on ignition, and
- asbestos.

MassDEP agrees that our goal should be to develop alternative uses for wood beyond landfill-dependent uses. However, in the interim there is a need for landfill-related uses. MassDEP believes that these current market outlets, along with future market development potential for wood, provide a suitable basis for including both “clean” and treated wood in the C&D ban.

**Gypsum Wallboard:** The primary concern with gypsum wallboard is that it can cause hydrogen sulfide generation and odors, particularly when ground up in fines or residuals and used as landfill cover or grading and shaping material. MassDEP will continue working with gypsum wallboard manufacturers on their commitment to develop recycling capacity for gypsum wallboard and with the construction industry to develop programs to recycle clean gypsum wallboard from construction sites. As markets develop for wallboard recycling, MassDEP will consider adding gypsum wallboard as an additional material under MassDEP’s waste ban regulations. This would require regulatory revisions.

**Asphalt Shingles:** MassDEP will take a similar approach with shingles as with gypsum wallboard. MassDEP will work to stimulate the development of additional recycling markets and diversion opportunities in advance of potentially adding shingles to the list of waste ban materials. This would require regulatory revisions.

### **C&D Waste Reduction Initiatives**

#### NEW

- **Publish Hydrogen Sulfide Landfill Guidance:** MassDEP will publish draft guidance on controlling hydrogen sulfide emissions from landfills and inactive landfill closures. MassDEP will accept public comment on this guidance prior to finalizing it. This will build on MassDEP’s experience with addressing significant problems at several landfill closure projects over the past several years.
- **Improve C&D Materials Management:** With input from C&D processors and other stakeholders, MassDEP will develop a set of strategies and action steps to improve the management of C&D fines and residuals, including reducing the amount of C&D fines and residuals that are produced by diverting materials to higher end uses.
- **C&D Project Review Team:** MassDEP will establish a project review team with high level management participation to clarify and expedite review processes for projects proposing to use C&D derived materials.

REVISED/EXPANDED

- **Build C&D Product Stewardship Initiatives:** MassDEP will work with manufacturers of construction materials to develop and build product stewardship initiatives where possible. This will include supporting the implementation of existing manufacturer commitments for carpet and wallboard and exploring product stewardship initiatives for other materials. When voluntary product stewardship initiatives are not successful, MassDEP will pursue regulatory controls such as waste bans more aggressively.
- **C&D Capacity Analysis:** MassDEP will prepare additional capacity analyses for C&D, including the projected capacity of inactive landfill closure projects and landfill daily cover uses. These capacity analyses will also address management of other materials such as contaminated soils and dredge spoils that may be used for landfill related uses.
- **Oversee Inactive Landfill Closures:** MassDEP will continue to oversee inactive landfill closure projects. As part of this effort, MassDEP will reassess existing landfill closure policies and beneficial use determination requirements to ensure that they are properly addressing management of residual C&D materials. In particular, MassDEP will consider whether the organic content standard for these materials should be lowered.

CONTINUED

- **Promulgate and Implement C&D Waste Ban:** MassDEP promulgated revisions to 310 CMR 19.000, the solid waste permitting regulations, that included a disposal ban on asphalt pavement, brick, concrete, wood, and metal. This ban is expected to have the greatest effect on increasing diversion of wood, since asphalt paving, brick, concrete and metal are already recycled at high rates. To support the ban, MassDEP has revised its waste ban guidance and held trainings on the ban, and will review and approve revised facility waste ban plans. Because the ban is focused on construction waste rather than residential materials, loads from transfer stations that only accept loads of less than 5 cubic yards (the size of a small dump truck) are exempt from the C&D waste ban and can be consolidated and sent for disposal. Under the ban, wood is allowed to be disposed at municipal waste combustion facilities.

Over time, MassDEP will explore adding other C&D materials to the list of banned materials as markets for those materials develop and grow. Potential additional banned materials include asphalt shingles, gypsum wallboard, and carpet. Any extension of the waste bans would require a regulatory change with public hearing and comment.

- **Promote C&D Market Development:** MassDEP will continue to use financial incentives such as Recycling Industry Reimbursement Credit grants and Recycling Loan Fund loans to promote development of new processing outlets and end markets for C&D materials.

- **C&D Waste Reduction Outreach:** MassDEP will continue outreach on C&D waste reduction for the construction and demolition industries by distributing information via MassDEP's C&D web page and by speaking at conferences and workshops.
- **SWAC C&D Subcommittee and Workgroups:** MassDEP will continue to hold meetings of its SWAC C&D Subcommittee and Subcommittee workgroups on an as-needed basis.

### **Toxicity Reduction Strategy**

Reducing the toxicity of the waste stream poses unique challenges. To make significant progress in this area requires either significant state or local funding or aggressive product stewardship initiatives, neither of which is in place in Massachusetts. Therefore, MassDEP's toxicity reduction strategy is to maintain existing progress and seek limited new initiatives for products that contain high priority substances such as mercury, lead and arsenic. As with other waste reduction strategies, MassDEP will seek to build partnerships among local governments, with business groups, and with other state agencies and universities to achieve these goals as cost-effectively as possible.

### **Toxicity Reduction Initiatives**

#### NEW

- **Toxics Use Reduction Assistance, Research, and Technology Development:** MassDEP will support the Office of Technical Assistance (OTA) and the Toxics Use Reduction Institute (TURI) programs to test and promote alternatives to toxic chemicals used in Massachusetts industries and communities. These efforts will emphasize chemicals such as mercury, lead, and arsenic that have been identified as High Priority Substances that may be contained in products disposed of as solid waste. These program efforts include extensive workshops, training sessions, industry dialogues and facility site visits. MassDEP will continue to work with TURI and OTA to monitor new issues and opportunities for reducing toxics in products that may be disposed as solid waste.
- **Toxics Use Reduction Act Reporting and Planning:** Although the focus of the Toxics Use Reduction Act (TURA) is on reducing the use of toxic chemicals and their associated releases, risks, and costs in industrial processes, TURA facilities have significantly reduced the amount of toxics shipped in products, some of which end up in landfills or combustion facilities. Within the 2000 TURA Core Group (facilities that were required to report in 2000 and 2003), facilities reduced the amount of toxic chemicals shipped in product by 11 percent, after adjusting for a decrease in production. From 1990 to 2003, facilities in the 1990 Core Group reduced the amount of toxic chemicals shipped in products by 68 percent after adjusting for production increases. MassDEP will continue to work with the Toxics Use Reduction Institute and the Office of Technical Assistance to implement the TURA program and further reduce the amount of toxic chemicals shipped in products.



## Solid Waste Master Plan: 2006 Plan Revision

- **TURI Five Chemicals Study:** In FY06, TURI received funding to conduct an alternatives assessment of five chemicals that will identify the most significant uses of the chemicals and assess safer alternatives for these uses. The five chemicals are lead, formaldehyde, perchloroethylene, hexavalent chromium, and di(2-ethylhexyl) phthalate (DEHP), many of which are contained in products that can end up in the solid waste stream. TURI must report back to the Legislature on the study results by July 2006. Additional information on this study can be found on TURI's web site at [www.turi.org](http://www.turi.org).
- **Supply Chain Initiatives:** TURI has convened supply chain working meetings to learn about new trade issues and technologies and to design new safer products to be competitive in changing markets. Efforts to date have included:
  - Exploring alternatives that would eliminate or reduce the use of lead and brominated flame retardants in the coated wire industry.
  - Developing lead-free solder applications for electronics.
- **Lowell Center for Sustainable Production:** The Lowell Center's Sustainable Production and Consumption Program works to promote sustainability in *all* of the life cycle phases of a product or service — including purchase, use, manufacture, and disposal. MassDEP will partner with solid waste-related components of the Lowell Center's Sustainable Hospitals program.
- **Healthy Lawn and Landscape Workshops:** MassDEP will continue to hold Healthy Lawn and Landscape Workshops that educate residents on pesticide use and ways to reduce use of fertilizers and pesticides through alternative lawn care practices, which reduce the need to manage leftover materials at hazardous product collection events.
- **Toxics Use Reduction Grants:** MassDEP will continue to partner with TURI on their Toxics Use Reduction Network grants to support toxics use reduction and pollution prevention on the local level. Recent grants have focused on pesticides use reduction.

### REVISED/EXPANDED

- **Provide Regional Program Coordination and Technical Assistance:** Through Municipal Assistance Coordinators, MassDEP will work with cities and towns to maintain cost-effective collection programs to provide ongoing access for residents to safely dispose of hazardous products. These efforts will focus on organizing shared regional and reciprocal collection programs that provide a basic level of access at a relatively low cost to participating towns.

### CONTINUED

- **Oversee Municipal Waste Combustor Material Separation Plans:** MassDEP will continue to work with municipal waste combustors and their contract municipalities to ensure that Material Separation Plans (MSPs) for mercury are implemented and revised as needed to maximize diversion and safe management of mercury-containing products from the waste stream. These plans focus on initiatives such as:

## Solid Waste Master Plan: 2006 Plan Revision

- Collection programs for residents, schools, and businesses for products such as fluorescent lamps, thermostats, and batteries.
  - Education and outreach on mercury-containing products.
  - Thermometer exchanges.
  - School mercury cleanouts.
- **Support School Chemical Management Programs:** MassDEP will provide grants, training, information, and guidance to school systems on improving chemical purchasing, storage, use and management practices to reduce the use of hazardous chemicals and ensure proper disposal.
- **State Hazardous Product Collection Contracts:** MassDEP will continue to work with the Operational Services Division to maintain statewide contracts that support municipal hazardous product collection programs, eliminating the need for municipalities to go out to bid for collection events themselves.
- **State Sustainability Toxics Use Reduction:** MassDEP will continue to work with the State Sustainability Program and Operational Services Division to increase purchases of lower-toxicity and less hazardous products by state agencies and authorities. MassDEP will also partner with the Toxics Use Reduction Institute's (TURI's) efforts to support the development of environmentally preferable cleaning products.

### **3: WASTE MANAGEMENT CAPACITY AND FACILITY OVERSIGHT**

#### **Waste Management Capacity**

Massachusetts has sought to maintain enough solid waste management capacity to manage its own waste. However, due to various factors, including regional market conditions, Massachusetts has been a net exporter of waste for several years, and this trend is expected to continue.

In 2004, Massachusetts generated 13.9 million tons of solid waste, of which 12.4 million tons was managed through diversion (7.6 million tons) or in-state disposal (4.8 million tons), while 1.6 million tons was exported for disposal (on a net basis). Net export of waste represents final waste management capacity that is not available within Massachusetts.

MassDEP has projected a range of future in-state management capacity and net export depending on whether recycling remains flat or grows to meet the 56% recycling goal in 2010<sup>14</sup>. Due primarily to shrinking in-state landfill capacity, projections for 2010 show a net export of between 2.5 million tons (if recycling remains flat) and 1.1 million tons (if recycling meets the 56% goal).

Figure 4, on page 41, shows two projected waste management capacity scenarios through 2010, using actual 2004 solid waste data as a starting point. These scenarios show the likely range of net export of waste depending on whether the recycling rate remains flat or increases to meet the goal of 56% recycling by 2010.

The “Baseline Recycling” scenario assumes that recycling tonnage will increase at the same rate as waste generation (2% per year), which results in the highest net export that would be expected in 2010, or 2.1 million tons. Projected net export would rise to 3.1 million tons by 2012 due to additional projected landfill closures. In this scenario, recycling tonnage increases keep pace with generation but recycling rates remain flat.

The “Increased Recycling” scenario assumes recycling tonnage will increase 4.3% per year to meet the 56% recycling goal, which results in the lowest net export that would be expected in 2010, or 1.0 million tons. In this scenario, projected net export rises to 1.9 million tons by 2012.

The data underlying these scenarios are shown in Table 13 on page 42. These scenarios also use the following assumptions:

- Generation tonnage will increase 2% per year, based on historical generation trends.
- Other Diversion of C&D (wood for fuel, fines for daily cover, and grading and shaping materials) will increase 2% per year, staying level with generation.
- Combustion capacity will remain constant at 2003 operating capacity.
- Landfill capacity will include currently permitted landfill capacity and landfill expansions that are planned but not yet permitted. Both current and potential landfill capacity

---

<sup>14</sup> In this scenario, the recycling rate remains level after 2010, with recycling tonnage increasing at the same rate as generation.

assumes landfills will operate at 81% of permitted capacity, based on historical trends of operating capacity. Table 12, on page 37, lists active landfill projects. Un-shaded numbers reflect currently permitted capacity. Shaded numbers reflect potential additional capacity that could be constructed based on existing facility plans, but is not yet permitted.

### **No Net Import/Export Policy**

The *Beyond 2000 Solid Waste Master Plan* established a policy goal of achieving no net import or export of solid waste by 2006. Under this policy, MassDEP would permit additional landfill disposal capacity up to, but not beyond, the amount of waste requiring disposal. Given the lack of significant additional solid waste management capacity coming on line in recent years and projections that net export will continue over the coming decade, MassDEP recognizes that Massachusetts will continue to be a net exporter of waste for the foreseeable future.

MassDEP believes that there are important benefits to striving towards a balanced waste management system, including making Massachusetts less vulnerable to changes in available disposal capacity in other states. Therefore, MassDEP will maintain a long-term goal of reaching no net import/export, but will not attach a milestone date to this goal. This change recognizes that regional markets are the primary driver of waste management capacity development decisions and that a significant export infrastructure has developed over the past several years to handle waste generated in Massachusetts. It also recognizes the difficulty of siting and permitting new disposal capacity in Massachusetts. MassDEP will continue to assess and plan for the Commonwealth's solid waste management needs, but will focus its resources on promoting waste reduction while relying on markets to ultimately guide capacity decisions.

MassDEP recognizes that transport of waste by rail is an appropriate part of waste management infrastructure, and that transport by rail is likely to grow as in-state disposal capacity decreases. Rail haul facilities that function as waste handling facilities, processing facilities or transfer stations where waste is dumped and stored, processed, shredded, baled or subjected to any other activity that is not integral to a railroad operation are subject to Massachusetts solid waste facility regulations and require site assignment by the local board of health and permitting by MassDEP. MassDEP also acknowledges that facilities where waste is transferred to rail cars only in inter-modal containers are not subject to Massachusetts solid waste facility regulation.

### **In-state Waste Management Capacity Need**

MassDEP has maintained the goal of disposing of only the "irreducible minimum" amount of waste and will continue to promote increased waste reduction through its various waste reduction programs. MassDEP will place special emphasis on supporting the development of additional in-state organics processing capacity, which can help businesses, cities and towns save money, reduce pressure on disposal capacity, create a valuable product, and support creation of additional jobs in Massachusetts. In addition, MassDEP will:

## Solid Waste Master Plan: 2006 Plan Revision

- Provide resources and information to support local Boards of Health responsible for reviewing proposals for processing facilities. This would include generic, statewide information for different categories of facilities, including the statewide benefits, typical facility profiles, local impacts to address, and best management practices.
- Ensure that current and future facilities operate soundly by providing information on best management practices and enforcing against poorly operated facilities to prevent nuisance impacts.
- Explore ways that MassDEP can stimulate increased organics processing capacity.
- Develop and provide capacity analyses for C&D and organics waste-streams, in addition to MassDEP's disposal capacity analysis.
- Continue to monitor the management of other material streams such as contaminated soils, dredge sediments, and coal ash that, while not typically managed as solid waste, may have implications for solid waste management capacity.
- Review and update as necessary components of the State's Disaster Debris Management Plan to support the Solid Waste Master Plan.

### **Disposal Capacity**

Unless and until net export drops dramatically, MassDEP will no longer limit allocation of disposal capacity for new or expanded landfills. MassDEP will review all landfill proposals based solely on site assignment and permitting requirements.

MassDEP will maintain the municipal waste combustion moratorium to maintain progress that has been made in reducing mercury emissions under the state's Zero Mercury Action Plan.

The seven municipal waste combustors emitted an estimated 558 pounds of mercury in 2002, 329 pounds in 2003, and 385 pounds in 2004. Despite significant reductions in mercury emissions over the past several years, municipal waste combustors continue to represent the largest in-state source of mercury emissions in Massachusetts compared to other sources.<sup>15</sup> These reductions have resulted in measurable environmental improvements. MassDEP recently finished a study in the Merrimack Valley showing that several years after local mercury emissions (primarily from MWCs) went down, mercury concentrations in fish tissue showed a significant decrease. MassDEP wants to ensure that this progress is maintained and furthered, and believes that allowing additional municipal waste combustion at this time could jeopardize this progress.

MassDEP believes that further expanding municipal waste combustion capacity, which already represents nearly 50 percent of Massachusetts total disposal capacity and 65 percent of in-state disposal capacity, is inconsistent with the New England Governors/Eastern Canadian Premiers' Mercury Action Plan and EOEA's Zero Mercury Action Plan, which have as a goal the virtual elimination of mercury emissions.

---

<sup>15</sup> *Inventory of Anthropogenic Mercury Emissions in the Northeast*, NESCAUM, November 2005. Data reported by MWCs for calendar year 2003 and 2004 under the Toxics Use Reduction Act.

## **Solid Waste Regulations, Permitting, and Compliance and Enforcement**

Since the *Beyond 2000 Plan* was issued, MassDEP promulgated major revisions to the Site Assignment regulations (310 CMR 16.000) and to the Permitting regulations (310 CMR 19.000). MassDEP also developed several guidance documents supporting these regulatory changes. These regulatory and guidance documents maintain the policy framework established in the *Beyond 2000 Plan* and include:

- Beneficial Use Determination (BUD) regulations and guidance that eliminate the one-size-fits-all approach and replace it with an approach tailored to the type of use proposed and the potential impacts from the use of a material. This guidance includes risk criteria for various contaminants.
- Expanding the waste bans to Construction and Demolition (C&D) wastes, including asphalt paving, brick, concrete, metal and wood. MassDEP has issued revised waste ban guidance to assist with implementation of the new waste bans.
- Updating landfill liner requirements to require double composite liners for new landfills and expansions. This will include revising the Landfill Technical Guidance Manual to address the revisions to the liner requirements

MassDEP is continuing to develop other approaches to effectively oversee solid waste facilities and materials management including:

- Developing guidance on addressing hydrogen sulfide emissions from landfills and inactive landfill closure projects. In cases in which landfills or closure projects accept C&D materials, this guidance will provide information on best management practices to avoid odor problems and health concerns. MassDEP expects to issue draft guidance for public review and input in 2006.
- Continuing to oversee inactive landfill closure projects. As part of this effort, MassDEP will reassess existing landfill closure policies to ensure that they are properly addressing management of residual C&D materials.
- Improving oversight and tracking of landfill gas emissions from both active and inactive landfills.
- Ensuring that waste haulers and generators, as well as solid waste facilities, are held accountable for compliance with the waste bans.
- Implementing a new sharps (i.e., needles, syringes) policy that builds on an earlier pilot program to make it easier and more cost-effective for boards of health and pharmacies to establish sharps collection locations for those who must administer home health care and to remove those sharps from the general solid waste and recycling streams for more appropriate management as infectious waste.

## 4: 2004 SOLID WASTE DATA

### 2004 Solid Waste Data and Waste Management Capacity Projections

To assist in implementing the *Beyond 2000 Solid Waste Master Plan*, MassDEP annually collects and analyzes solid waste management system data. The data are used to track progress in meeting waste reduction milestones and to evaluate waste management capacity needs. MassDEP has updated solid waste data through calendar year 2004 and revised waste management capacity projections through 2010 based on the 2004 data. A description of how MassDEP collects and analyzes solid waste data can be found in Appendix A. Briefly, MassDEP calculates the following rates:

Overall Waste Reduction Rate

$$= \frac{(\text{MSW Recycling}^{16} + \text{Source Reduction}^{17}) + (\text{C\&D Recycling} + \text{Source Reduction} + \text{Other Diversion})}{\text{Total Potential Generation}^{18}}$$

MSW Waste Reduction Rate

$$= \frac{\text{MSW Recycling} + \text{Source Reduction}}{\text{MSW Potential Generation}}$$

Non-MSW Waste Reduction Rate

$$= \frac{\text{Non-MSW Recycling} + \text{Source Reduction} + \text{C\&D Other Diversion}}{\text{Non-MSW Potential Generation}}$$

MSW Recycling Rate

$$= \frac{\text{MSW Recycling}}{\text{MSW Actual Generation} \\ (\text{Recycling} + \text{Disposal})}$$

C&D Recycling Rate

$$= \frac{\text{C\&D Recycling}}{\text{C\&D Actual Generation} \\ (\text{Recycling} + \text{Other Diversion} + \text{Disposal})}$$

C&D Diversion Rate

$$= \frac{\text{C\&D Recycling} + \text{C\&D Other Diversion}}{\text{C\&D Actual Generation} \\ (\text{Recycling} + \text{Other Diversion} + \text{Disposal})}$$

### Progress in Meeting Waste Reduction Milestones

Table 1 summarizes waste reduction rates from 2002-2004. Waste reduction includes source reduction (preventing waste from being generated), recycling (including composting), and other C&D diversion.<sup>19</sup> Total waste reduction increased from 57% in 2002 to 60% in 2004. Municipal solid waste (MSW) waste reduction increased from 40% in 2002 to 45% in 2004. Non-municipal solid waste (Non-MSW) waste reduction remained essentially flat, going from 86% in 2002 to 88% in 2004. While the non-MSW waste reduction rate has reached the 88% goal set in the *Beyond 2000 Master Plan*, MassDEP believes that Massachusetts still faces several important challenges in improving management of C&D materials, including the need to increase separation of materials to enable and stimulate higher-value end uses, reduce landfill-dependent reuse of C&D materials, and increase recycling rates of materials other than asphalt paving, brick, and concrete, such as wood, asphalt shingles, and gypsum wallboard, which currently are only recycled at a rate of 9%.

<sup>16</sup> MSW recycling includes both recycling and off site-composting, but does not include home composting, which is considered source reduction.

<sup>17</sup> Source reduction refers to the difference between potential generation and actual generation.

<sup>19</sup> For a discussion of how MassDEP measures waste reduction, see page 3-7 of the *Beyond 2000 Solid Waste Master Plan*.

<b>Table 1</b> <b>Waste Reduction Rates Based on <i>Potential</i> Generation<sup>20</sup></b>				
	<b>2002</b>	<b>2003</b>	<b>2004</b>	<b>2010 Milestone</b>
Total Waste Reduction Rate	57%	58%	60%	70%
MSW Waste Reduction Rate	40%	43%	45%	60%
Non-MSW Waste Reduction Rate	87%	86%	88%	88%

Table 2 shows recycling rates based on actual generation. Please see Figure 2 for a graphical description of generation, recycling, and disposal tonnage trends. Of the total waste that was generated 2004, 48% was recycled, an increase from 47% in 2002. The MSW recycling rate increased from 31% in 2002 to 35% in 2004. The C&D recycling rate decreased from 75% in 2002 to 71% in 2004.

<b>Table 2</b> <b>Recycling Rates Based on Actual Generation</b>			
	<b>2002</b>	<b>2003</b>	<b>2004</b>
Overall Recycling	47%	47%	48%
MSW Recycling *	31%	34%	35%
C&D Recycling	75%	71%	71%

\*Excludes backyard composting which is source reduction

## Environmental and Economic Benefits of Recycling

In 2004, Massachusetts prevented the disposal of 9.6 million tons of waste through a combination recycling, composting and other waste reduction, saving enough landfill space to eliminate the need for nearly 22 landfills each equal to the state's largest (1,200 tons per day). Waste reduction also slows global warming, conserves natural resources, saves energy, and prevents pollution. By recycling or composting municipal solid waste alone in 2004, Massachusetts is estimated<sup>21</sup> to have:

- Reduced greenhouse gas emissions by nearly 2.6 million tons of carbon equivalent per year.
- Saved 108 trillion BTUs of energy, equivalent to 18 million barrels of oil, or 870 million gallons of gasoline.
- Saved 1.6 million tons of iron ore, coal, and limestone and saved nearly 17 million trees.

<sup>20</sup> <sup>20</sup> Potential Generation is an estimate of the amount of waste expected based on economic activity. MassDEP uses Massachusetts Gross State Product (GSP) as the economic "driver" to estimate potential generation. Newly released GSP estimates for 1997 – 2003 have been updated to reflect 2000 real-chained dollar values and rely on NAICS definitions, whereas previous GSP estimates were in 1996 real-chained dollar values and relied on SIC codes. This change has resulted in slightly higher waste reduction rates for previously published data.

<sup>21</sup> Source: *Recycling Environmental Impacts Model*, Northeast Recycling Council, December 2004. The increase in savings from 2002 is due to methodology changes in the model.



## Solid Waste Master Plan: 2006 Plan Revision

In addition, recycling bolsters the state's economy. Recycling, reuse, and remanufacturing directly support 19,000 jobs in Massachusetts, maintain a payroll of nearly \$600 million, and bring in annual revenues of \$3.6 billion. Total direct and indirect economic activity from recycling, reuse, and remanufacturing is estimated to generate more than \$142 million annually in state revenues for Massachusetts<sup>22</sup>.

---

<sup>22</sup> *Recycling Economic Information Study*, prepared for the Northeast Recycling Council by R.W. Beck, Inc, June 2000.

# Solid Waste Master Plan: 2006 Plan Revision

## Solid Waste Management 2000 – 2004

Table 3 presents a comprehensive picture of solid waste management in Massachusetts for calendar years 1999-2004. Table 3a highlights how solid waste management changed from 2003 to 2004.

Table 3							
Integrated Solid Waste Management System 2000-2004							
			2000	2001	2002	2003	2004
<b>Potential Generation</b>			<b>14,850,000</b>	<b>14,660,000</b>	<b>14,440,000</b>	<b>15,250,000</b>	<b>15,990,000</b>
	MSW		9,520,000	9,380,000	9,260,000	9,800,000	<b>10,280,000</b>
	Non-MSW		5,330,000	5,250,000	5,180,000	5,450,000	<b>5,710,000</b>
<b>Source Reduction</b>			<b>2,040,000</b>	<b>1,880,000</b>	<b>1,200,000</b>	<b>2,040,000</b>	<b>2,050,000</b>
	MSW		1,530,000	1,270,000	900,000	1,340,000	<b>1,550,000</b>
	Non-MSW		510,000	610,000	300,000	700,000	<b>500,000</b>
<b>Total Generation</b>			<b>12,960,000</b>	<b>12,780,000</b>	<b>13,240,000</b>	<b>13,210,000</b>	<b>13,930,000</b>
MSW			7,990,000	8,130,000	8,350,000	8,460,000	8,720,000
		Residential	3,130,000	3,130,000	3,300,000	3,520,000	3,510,000
		Commercial	4,860,000	5,000,000	5,050,000	4,940,000	5,210,000
Non-MSW			4,970,000	4,650,000	4,890,000	4,750,000	5,210,000
		C&D	4,480,000	4,540,000	4,820,000	4,720,000	5,160,000
		Other	490,000	110,000	70,000	30,000	50,000
<b>Diversions</b>			<b>6,500,000</b>	<b>6,440,000</b>	<b>6,790,000</b>	<b>6,860,000</b>	<b>7,580,000</b>
MSW			2,700,000	2,780,000	2,610,000	2,870,000	3,070,000
		Residential Recycling	470,000	520,000	520,000	540,000	540,000
		Commercial Recycling	1,640,000	1,640,000	1,400,000	1,660,000	1,880,000
		Residential Composting	340,000	340,000	330,000	350,000	340,000
		Commercial Composting	250,000	280,000	360,000	330,000	310,000
Non-MSW			3,800,000	3,660,000	4,180,000	3,990,000	4,500,000
		C&D	3,500,000	3,150,000	3,590,000	3,360,000	3,650,000
		Other C&D Diversion	300,000	510,000	590,000	630,000	860,000
<b>Disposal</b>			<b>6,460,000</b>	<b>6,340,000</b>	<b>6,450,000</b>	<b>6,340,000</b>	<b>6,360,000</b>
	Landfill		1,760,000	1,710,000	1,790,000	1,710,000	1,720,000
		MSW	1,010,000	1,030,000	1,210,000	1,310,000	1,430,000
		C&D	660,000	620,000	520,000	370,000	270,000
		Other	90,000	60,000	60,000	20,000	30,000
	Combustion		3,070,000	3,130,000	3,090,000	3,130,000	3,080,000
		MSW	3,060,000	3,130,000	3,080,000	3,120,000	3,070,000
		Non-MSW	*0	*0	*0	*0	*0
	<i>Net Exports</i>		<i>1,630,000</i>	<i>1,500,000</i>	<i>1,570,000</i>	<i>1,510,000</i>	<i>1,560,000</i>
		<i>Exports</i>	<i>1,770,000</i>	<i>1,690,000</i>	<i>1,830,000</i>	<i>1,790,000</i>	<i>1,840,000</i>
		<i>Imports</i>	<i>140,000</i>	<i>190,000</i>	<i>250,000</i>	<i>280,000</i>	<i>280,000</i>
*Non-MSW combustion was less than 5,000 tons							

\*Non-MSW combustion was less than 5,000 tons. Note: Numbers do not all add exactly due to rounding.


Solid Waste Master Plan: 2006 Plan Revision

Table 3a: Tonnage and Percent Change Summary: 2003-2004							
			2003	2004	Tons Change	% Change	
<b>Potential Generation</b>			<b>15,250,000</b>	<b>15,990,000</b>	<b>740,000</b>	<b>4.9%</b>	
	MSW		9,800,000	10,280,000	480,000	4.9%	
	Non-MSW		5,450,000	5,710,000	260,000	4.8%	
<b>Source Reduction</b>			<b>2,040,000</b>	<b>2,050,000</b>	<b>10,000</b>	<b>0.5%</b>	
	MSW		1,340,000	1,550,000	210,000	15.7%	
	Non-MSW		700,000	500,000	(200,000)	-28.6%	
<b>Total Generation</b>			<b>13,210,000</b>	<b>13,930,000</b>	<b>720,000</b>	<b>5.5%</b>	
<b>MSW</b>			<b>8,460,000</b>	<b>8,720,000</b>	<b>260,000</b>	<b>3.1%</b>	
		Residential	3,520,000	3,510,000	(10,000)	-0.3%	
		Commercial	4,940,000	5,210,000	270,000	5.5%	
<b>Non-MSW</b>			<b>4,750,000</b>	<b>5,210,000</b>	<b>460,000</b>	<b>9.7%</b>	
		C&D	4,720,000	5,160,000	440,000	9.3%	
		Other	30,000	50,000	20,000	66.7%	
<b>Diversion</b>			<b>6,860,000</b>	<b>7,580,000</b>	<b>720,000</b>	<b>10.5%</b>	
<b>MSW</b>			<b>2,870,000</b>	<b>3,070,000</b>	<b>200,000</b>	<b>7.0%</b>	
		Residential Recycling	540,000	540,000	-	0.0%	
		Commercial Recycling	1,660,000	1,880,000	220,000	13.3%	
		Residential Composting	350,000	340,000	(10,000)	-2.9%	
		Residential On Site Composting	590,000	580,000	(10,000)	-1.7%	
		Commercial Composting	330,000	310,000	(20,000)	-6.1%	
<b>Non-MSW</b>			<b>3,990,000</b>	<b>4,500,000</b>	<b>510,000</b>	<b>12.8%</b>	
		C&D	3,360,000	3,650,000	290,000	8.6%	
		Other C&D Diversion	630,000	860,000	230,000	36.5%	
<b>Disposal</b>			<b>6,340,000</b>	<b>6,360,000</b>	<b>20,000</b>	<b>0.3%</b>	
	<b>Landfill</b>		<b>1,710,000</b>	<b>1,720,000</b>	<b>10,000</b>	<b>0.6%</b>	
		MSW	1,310,000	1,430,000	120,000	9.2%	
		C&D	370,000	270,000	(100,000)	-27.0%	
		Other	20,000	30,000	10,000	50.0%	
	<b>Combustion</b>		<b>3,130,000</b>	<b>3,080,000</b>	<b>(50,000)</b>	<b>-1.6%</b>	
		MSW	3,120,000	3,070,000	(50,000)	-1.6%	
		Non-MSW	-	-	-		
<b>Net Exports</b>			<b>1,510,000</b>	<b>1,560,000</b>	<b>50,000</b>	<b>3.3%</b>	
		Exports	1,790,000	1,840,000	50,000	2.8%	
		Imports	280,000	280,000	-	0.0%	
Note: % Change is calculated based on the rounded amounts in this table.							

## Solid Waste Master Plan: 2006 Plan Revision

In 2004, 13.9 million tons of solid waste were *actually* generated in Massachusetts. Of this amount, 8.7 million tons were MSW (63%) and 5.2 million tons were Non-MSW (37%). Generation increased by more than five percent from 2003 to 2004, from 13.2 million tons to 13.9 million tons. Of the 14.1 million tons generated, 7.6 million tons (54%) were diverted (includes recycling, composting, and other diversion) and 6.4 million tons (46%) were disposed.

**Figure 1**  
Total Solid Waste Generation in 2004



From 2000 to 2004, the amount of total waste requiring disposal decreased by 1.5%. From 2003 to 2004, total disposal increased slightly, by about 0.3%. 4.8 million tons (34%) of total waste generated were disposed in-state either by landfilling (27% of disposal) or by combustion (49% of disposal). In 2004, there were 21 landfills and 7 combustors operating in the state that received MSW and/or Non-MSW. The combustion facilities produce approximately 200 megawatts of electricity each year. The state exported for disposal 1.8 million tons and imported 0.3 million tons, and thus was a net exporter of 1.6 million tons (11%) of total waste generated. See Table 10 and 11 for more detailed import/export data by state.

Table 4 shows the calculation of total waste reduction in 2004. Waste Reduction is the combined effect of source reduction, recycling, and other C&D diversion as a percentage of *potential* waste generation. The 42 percent recycling rate shown below is lower than the overall 48 percent recycling rate because it is based on potential, rather than actual generation. This table shows that, while recycling continues to comprise most waste reduction tonnage, source reduction plays an important role, comprising 12% of potential waste generation in 2004.

<b>Table 4</b> <b>2004 Total Waste Reduction (in tons)</b>	
	<b>2004</b>
Potential Generation without Source Reduction	15,990,000
Source Reduction <i>% of potential generation</i>	2,050,000 13%
Recycling* <i>% of potential generation</i>	6,720,000 42%
C&D Other Diversion <i>% of potential generation</i>	860,000 5%
Total Waste Reduction <i>% of potential generation</i>	9,630,000 60%
* The recycling rate is 48% when based on <i>actual</i> generation.	

### Municipal Solid Waste Management

In 2004, 8.7 million tons of MSW were generated in Massachusetts, or 7.5 pounds per person per day, up from 7.4 pounds per person per day in 2003. Of this amount, 35% was recycled (including off-site composting, but excluding on-site backyard composting), which is an increase from 34% in 2003 and 31% in 2002. This increase can be attributed to an increase in recycling markets for some materials in 2003 and 2004. The per capita MSW recycling rate was 2.6 pounds per person per day, and the per capita disposal rate (including export) was 4.9 pounds per person per day. The residential MSW recycling rate (excluding home composting) was 25% and the commercial MSW recycling rate was 42%. Residential MSW generation (excluding commercial waste) in 2004 was 3,510,000 tons, an average of 3.0 pounds per person per day.

<b>Table 5</b> <b>How MSW was managed from</b> <b>2002-2004</b>			
	<b>2002</b>	<b>2003</b>	<b>2004</b>
<b>Recycled</b>	31%	34%	35%
<b>Combusted</b>	37%	37%	35%
<b>Landfilled</b>	15%	15%	16%
<b>Net Exported</b>	17%	14%	14%

Between 2003 and 2004:


- MSW generation increased 4%, from 8.4 million tons to 8.7 million tons. Per capita MSW generation rose from 7.1 pounds per person per day to 7.5 pounds per person per day.
- Residential MSW generation increased 6%, from 3.3 million tons to 3.5 million tons, while commercial MSW generation increased 3%, from 5.1 million tons to 5.2 million tons.

## Solid Waste Master Plan: 2006 Plan Revision

- MSW recycling (including composting) increased 18%, from 2.6 million tons to 3.1 million tons. This was primarily due to increased commercial recycling, whereas residential recycling and composting only increased 4 percent during this two-year period.
- Total MSW disposal (disposal in-state and exported out of state for disposal) remained about the same at 5.7 million tons.
- MSW net exports for disposal decreased about 20%, from 1.5 million tons to 1.2 million tons.

Solid Waste Master Plan: 2006 Plan Revision

**Figure 2**  
**Generation, Recycling and Disposal Trends**



**Figure 3**  
Breakdown of MSW Materials Recycled in 2004  
(excluding composting)

**Total Materials Recycled: 2.4 Million Tons**




Table 6 shows the calculation of MSW waste reduction in 2004. Waste reduction is the combined effect of source reduction and recycling as a percentage of *potential* waste generation.

<b>Table 6</b>	
<b>2004 MSW Waste Reduction (in tons)</b>	
	<b>2004</b>
Potential MSW Generation without Source Reduction	10,280,000
Source Reduction	1,550,000
<i>% of potential generation</i>	15%
Recycling*	3,070,000
<i>% of potential generation</i>	30%
Total Waste Reduction	4,620,000
<i>% of potential generation</i>	45%
*The recycling rate is 35% when based on <i>actual</i> MSW generation	
Note: percentages do not add exactly due to rounding.	



## Solid Waste Master Plan: 2006 Plan Revision

Municipal recycling rates by year are shown in Table 7. This table shows that the distribution of municipal recycling rates has not changed substantially over the past five years. *(Note: MassDEP did not collect FY02 municipal recycling data because it switched to a calendar year datasheet time frame to match other solid waste reporting.)*

<b>Table 7</b> <b>Municipal Recycling Rates</b>					
<b>Municipalities Achieving:</b>	<b>FY2000</b>	<b>FY2001</b>	<b>CY 2002</b>	<b>CY2003</b>	<b>CY2004</b>
30% or greater	162	182	181	162	156
20-29%	68	73	61	86	78
10-19%	40	34	41	41	41
5-9%	2	7	5	11	8
Not included due to incomplete or missing data	79	55	63	51	68

### **Non-MSW Waste Management**

In 2001, MassDEP added a new category called “C&D Other Diversion” to account for materials such as C&D fines and wood for fuel used for beneficial uses. In 2002, an additional material, “C&D residuals”, was added to account for materials used for grading and shaping at landfill closure projects that began in 2002. This tonnage is counted as generation, but not as recycling or disposal since this use is not considered to be either recycling or disposal. However, these activities are considered diversion since they divert material from disposal and free up capacity for other materials.

In 2004, 5.2 million tons of C&D were generated in Massachusetts, up from 4.7 million tons in 2003. Of the amount generated, 71% was recycled, the same as in 2003. Including C&D Other Diversion with recycling, the overall C&D diversion rate was 88% in 2004. Table 8 shows how C&D was managed 2002 – 2004.

<b>Table 8</b> <b>C&amp;D Management in 2002 -2004</b>			
	<b>2002</b>	<b>2003</b>	<b>2004</b>
<b>Generated</b>	<b>4,750,000</b>	<b>4,720,000</b>	<b>5,160,000</b>
<b>Disposed</b>	<b>620,000</b>	<b>720,000</b>	<b>660,000</b>
• <b>In-State</b>	520,000	370,000	270,000
• <b>Out-of-State</b>	100,000	350,000	390,000
<b>Diverted</b>	<b>4,130,000</b>	<b>3,990,000</b>	<b>4,500,000</b>
• <b>Recycled</b>	<b>3,540,000</b>	<b>3,360,000</b>	<b>3,650,000</b>
o <i>Asphalt, Brick, and Concrete (ABC)</i>	3,280,000	3,200,000	3,470,000
o <i>Metal</i>	50,000	80,000	100,000
o <i>C&amp;D wood</i>	40,000	20,000	30,000
o <i>Wood Waste</i>	110,000	40,000	50,000
o <i>Other*</i>	60,000	20,000	20,000
• <b>C&amp;D Other Diversion</b>	<b>590,000</b>	<b>630,000</b>	<b>860,000</b>
o <b>C&amp;D Fines/Residuals</b>	460,000	540,000	810,000
o <b>C&amp;D Wood for Fuel</b>	130,000	90,000	50,000

\*Other materials include ceiling tiles, carpet, gypsum wallboard, and asphalt roofing shingles. Table 9 shows the calculation of non-MSW waste reduction in 2004. Waste reduction is the combined effect of recycling, source reduction and other C&D diversion as a percentage of *potential* generation.

<b>Table 9</b> <b>2004 Non-MSW Waste Reduction (in tons)</b>	
	<b>2004</b>
Potential generation without source reduction	5,710,000
Source Reduction	500,000
<i>% of potential generation</i>	9%
Recycling*	3,650,000
<i>% of potential generation</i>	64%
C&D Other Diversion	860,000
<i>% of potential generation</i>	15%
Total Waste Reduction	5,000,000
<i>% of potential generation</i>	88%
* The recycling rate is 71% based on <i>actual</i> generation.	
Note: percentages do not add exactly due to rounding.	

### Other Non-MSW Management

A relatively small amount of non-MSW materials other than C&D are disposed in Massachusetts landfills or sent out of state for disposal each year. In 2004, 30,000 tons of these materials were disposed including industrial waste, medical waste, wood waste, ash and sludge.

In addition, a significant amount of other non-MSW materials are managed each year in management systems that have in the past been tracked separately from the primary MSW/C&D waste management system. These include MSW combustion ash disposal, use of materials as alternative daily cover at landfills (both active and inactive), and other beneficial uses of materials in non-landfill applications.

### Materials Used for Daily Cover

Table 10 shows materials used as daily cover at landfills.

<b>Table 10</b> <b>Reported Daily Cover Material at Active Landfills</b> <b>(in tons)<sup>23</sup></b>			
	<b>2002</b>	<b>2003</b>	<b>2004</b>
<b>Auto Shredder Residue</b>	120,000	20,000	50,000
<b>Soil/Sand</b>	270,000	180,000	230,000
<b>Contaminated Soils</b>	180,000	140,000	280,000
<b>C&amp;D Fines</b>	230,000	300,000	300,000
<b>Other Materials<sup>24</sup></b>	310,000	300,000	240,000
<b>TOTAL</b>	<b>1,100,000</b>	<b>940,000</b>	<b>1,100,000</b>

### Municipal Waste Combustor Ash

Seven waste-to-energy combustors operated in Massachusetts in 2004. In 2004, these combustors generated approximately 790,000 tons of combustion ash (excluding recovered post-burn metals), 90,000 of which was beneficially reused and 700,000 tons of which was disposed of in six<sup>25</sup> combustion ash mono-fills located in Massachusetts. A number of these mono-fills are nearing their capacity, and efforts are underway by a number of combustors to expand capacity. The current status of these ash landfills is summarized in Table 11.

<b>Table 11</b> <b>Active MSW Combustion Ash Landfills</b>		
<b>Municipality</b>	<b>Site Name</b>	<b>Current Permit Expires</b>
Agawam	Bondi's Island Ash Landfill	2009
Peabody	Peabody Ash Landfill	2006
Saugus	Wheelabrator Ash Landfill	2008
Haverhill	Ward Hill Neck Ash Landfill	2009
Shrewsbury	Shrewsbury Ash Landfill	2013
Carver	CMW Ash Landfill	2013

<sup>23</sup> Daily Cover tonnages have been revised for consistency across time, and do not include material disposed at Quarry Hills, since this is not an active landfill.

<sup>24</sup> "Other Materials" includes approximately 20 various materials such as ground asphalt and DPW wastes.

<sup>25</sup> One of the 7 waste-to-energy combustors sends its combustion ash out of state.

## Solid Waste Master Plan: 2006 Plan Revision

Tables 12 and 13 show MSW and C&D export and import data by state. The export and import data for Massachusetts was collected from annual facility reports (AFR) submitted to MassDEP and from calling other states directly. In some instances, the MSW export data provided in the AFR differed from that reported from the states. In order to make the most conservative estimate of export, the higher number from the two sources was used. For example, if an AFR reported that Massachusetts sent Connecticut 10,000 tons of MSW, and Connecticut reported receiving 29,000 tons of MSW, 29,000 tons of export was used. The C&D import and export data is strictly from the AFRs, as confirmation from other states was not available at time of preparing this document.

<b>Table 8</b>			
<b>MSW Export by State: 2002-2004</b>			
	<b>2002</b>	<b>2003</b>	<b>2004</b>
<b>CT</b>	40,168	39,088	39,060
<b>ME</b>	290,977	222,957	230,686
<b>NH</b>	318,129	301,022	186,000
<b>NY</b>	380,000	193,817	277,716
<b>OH</b>	98,253	120,450	130,284
<b>PA</b>	14,375	5,039	3,695
<b>RI</b>	32	5,984	6,223
<b>SC</b>	401,318	446,351	492,295
<b>VA</b>	1,785	12,107	3,696
<b>VT</b>			4,195
<b>Canada</b>			
<b>Other Unknown</b>		43	
<b>TOTAL</b>	<b>1,545,037</b>	<b>1,366,858</b>	<b>1,374,918</b>

<b>Table 8a.</b>			
<b>MSW Import by State: 2002-2004</b>			
	<b>2002</b>	<b>2003</b>	<b>2004</b>
<b>CT</b>	24,320	60,969	53,028
<b>ME</b>	8,759	9,066	20,787
<b>NH</b>	25,483	26,426	41,027
<b>NY</b>	8,883	77,530	73,473
<b>RI</b>	14,438	24,539	26,155
<b>VT</b>	4,924	4,627	5,475
<b>Canada</b>	978		
<b>TOTAL</b>	<b>87,785</b>	<b>203,157</b>	<b>219,945</b>

<b>Table 9</b> <b>C&amp;D Export by State: 2002-2004</b>			
	<b>2002</b>	<b>2003</b>	<b>2004</b>
<b>CT</b>	18,452	5,404	1,117
<b>ME</b>	49,414	148,317	137,751
<b>NH</b>	4,991	14,410	11,713
<b>NY</b>	60,508	19,591	17,965
<b>OH</b>	138,398	180,702	240,484
<b>PA</b>	474		1,912
<b>RI</b>	2,631	4,046	1,024
<b>SC</b>		31,933	32,403
<b>VA</b>		10,440	
<b>VT</b>	300	26	
<b>Canada</b>			
<b>Other Unknown</b>			
<b>TOTAL</b>	<b>275,168</b>	<b>414,869</b>	<b>444,369</b>

<b>Table 9a.</b> <b>C&amp;D Import by State: 2002-2004</b>			
	<b>2002</b>	<b>2003</b>	<b>2004</b>
<b>CT</b>	132,051	54,473	36,869
<b>ME</b>	12,690	983	
<b>NH</b>	5,481	2,414	10,205
<b>NY</b>	2,517	6,579	7,676
<b>RI</b>	736	34	626
<b>VA</b>	24		
<b>TOTAL</b>	<b>153,499</b>	<b>64,483</b>	<b>55,656</b>

Tables 14 and 15 detail all solid waste that was accepted and diverted through Massachusetts Transfer Stations in 2003 and 2004. This data is different from the import/export data reported above since it includes waste that was generated and disposed in Massachusetts in addition to the waste that was imported and exported. This data indicates the significant role that transfer stations play in managing Massachusetts' waste.

<b>Table 14</b> <b>Transfer Stations - Waste Accepted</b> <b>(rounded to nearest 1,000 tons)</b>		
<b>Waste Class</b>	<b>2003 Tons Accepted</b>	<b>2004 Tons Accepted</b>
C&D	471,000	524,000
MSW	2,405,000	2,440,000
MSW Recycling	243,000	233,000
Non-MSW	25,000	27,000
Sludge	1,000	2,000

Solid Waste Master Plan: 2006 Plan Revision

<b>Table 15</b> <b>Transfer Stations - Waste Diverted</b> <b>(rounded to nearest 1,000 tons)</b>		
<b>State Sent To</b>	<b>2003 Tons Sent for Diversion</b>	<b>2004 Tons Sent for Diversion</b>
MA	358,000	410,000
NH	17,000	8,000
CT	4,000	2,000
RI	3,000	3,000
ME	3,000	3,000
VT	1,000	<1,000
NJ	<1,000	<1,000
NY	<1,000	<1,000
Canada	<1,000	0

# Solid Waste Master Plan: 2006 Plan Revision

**Table 12**  
**Projected Landfill Capacity (Tons Per Year)**


Town	2003 Permitted Capacity	End of current permit	Lifetime of LF	Proposed change in tonnage	date of proposed change going online	new tonnage after new capacity	2004	2005	2006	2007	2008	2009	2010	2011	2012
Active Landfills															
Barre	93600	2007	2013	0	0	93600	93600	93600	93600	93600	93600	93600	93600	93600	93600
Bourne	219000	2006	2024	0	0	219000	219000	219000	219000	219000	219000	219000	219000	219000	219000
Carver	97982	2013	2013	0	0	97982	60000	60000	60000	60000	60000	60000	60000	60000	60000
Chicopee	365000	2007	2012	-145000	2004	220000	220000	220000	220000	220000	220000	220000	220000	220000	220000
Dartmouth	115000	2007	2021	0	0	115000	115000	115000	115000	115000	115000	115000	115000	115000	115000
Fall River*	490000	2006	2010	0	0	490000	490000	490000	490000	490000	490000	490000	490000	0	0
Gardner	93600	2005	2005	0	0	93600	93600	93600	0	0	0	0	0	0	0
Granby	146000	2008	2011	89000	2005	235000	146000	235000	235000	235000	235000	235000	235000	235000	0
Hardwick	82800	2007	2025	151200	2007	234000	82800	82800	82800	234000	234000	234000	234000	234000	234000
Hull	833	2006	2006	0	0	833	833	833	833	0	0	0	0	0	0
Middleborough	9620	2011	2011	0	0	9620	9620	9620	9620	9620	9620	9620	9620	9620	0
Nantucket	30000	2015	2015	0	0	30000	30000	30000	30000	30000	30000	30000	30000	30000	30000
Northampton	50000	2007	2007	0	0	50000	50000	50000	50000	50000	0	0	0	0	0
South Hadley	123260	2011	2016	0	0	123260	123260	123260	123260	123260	123260	123260	123260	123260	123260
Southbridge	180960	2019	2019	0	0	180960	180960	180960	180960	180960	180960	180960	180960	180960	180960
Sturbridge	410	2016	2016	0	0	410	410	410	410	410	410	410	410	410	410
Taunton	120120	2007	2015	0	0	120120	120120	120120	120120	120120	120120	120120	120120	120120	120120
Warren	2000	2005	2005	0	0	2000	2000	2000	0	0	0	0	0	0	0
Wayland	2345	2005	2011	0	0	2345	2345	2345	2345	2345	2345	2345	2345	2345	0
Westminster	156000	2007	2025	140400	2005	296400	156000	296400	296400	296400	296400	296400	296400	296400	296400
2378530															
TOTAL PERMITTED CAPACITY							2,373,930	2,462,930	2,364,985	1,806,352	677,232	442,232	442,232	442,232	309,352
TOTAL POTENTIAL CAPACITY							2,373,930	2,462,930	2,367,330	2,517,697	2,467,697	2,467,697	2,467,697	1,977,697	1,607,472

**KEY:**

Permitted Capacity	number without shading
Potential Additional Capacity	number with shading

\* DEP issued an Authorization to Construct the next phase of cells at Fall River; however, the city revoked the landfill's Site Assignment. BFI appealed the city's action, and the court ruled in favor of BFI. Construction of the cells has begun, but the city is appealing the court's decision, so it is uncertain when or if this additional capacity will go online.

**Figure 4: Waste Management Capacity Projections**





## Solid Waste Master Plan: 2006 Plan Revision

**Waste Management Capacity Projections - 56 % recycling in 2010**

	2004	2005	2006	2007	2008	2009	2010	2011	2012
<b>Total Generation</b>	<b>13,934,840</b>	<b>14,213,536</b>	<b>14,497,807</b>	<b>14,787,763</b>	<b>15,083,518</b>	<b>15,385,189</b>	<b>15,692,893</b>	<b>16,006,750</b>	<b>16,326,885</b>
<b>Baseline Recycling</b>	<b>6,717,586</b>	<b>6,851,937</b>	<b>6,988,976</b>	<b>7,128,756</b>	<b>7,271,331</b>	<b>7,416,757</b>	<b>7,565,092</b>	<b>7,716,394</b>	<b>7,870,722</b>
<b>Increased Recycling (to meet 56% goal)</b>		<b>167,940</b>	<b>346,795</b>	<b>537,126</b>	<b>739,515</b>	<b>954,577</b>	<b>1,182,951</b>	<b>1,206,610</b>	<b>1,230,743</b>
<b>Total Recycling (to meet 56% goal)</b>	<b>6,717,586</b>	<b>7,019,877</b>	<b>7,335,771</b>	<b>7,665,881</b>	<b>8,010,846</b>	<b>8,371,334</b>	<b>8,748,044</b>	<b>8,923,005</b>	<b>9,101,465</b>
<b>Increased Recycling Rate</b>	<b>48.2%</b>	<b>49.4%</b>	<b>50.6%</b>	<b>51.8%</b>	<b>53.1%</b>	<b>54.4%</b>	<b>55.7%</b>	<b>55.7%</b>	<b>55.7%</b>
<b>C&amp;D Other Diversion</b>	<b>877,637</b>	<b>895,190</b>	<b>913,094</b>	<b>931,355</b>	<b>949,983</b>	<b>968,982</b>	<b>988,362</b>	<b>1,008,129</b>	<b>1,028,292</b>
<b>Combustion Capacity</b>	<b>3,078,146</b>	<b>3,078,146</b>	<b>3,078,146</b>	<b>3,078,146</b>	<b>3,078,146</b>	<b>3,078,146</b>	<b>3,078,146</b>	<b>3,078,146</b>	<b>3,078,146</b>
<b>Potential LF Capacity</b>	<b>1,724,859</b>	<b>1,994,973</b>	<b>1,917,537</b>	<b>2,039,335</b>	<b>1,998,835</b>	<b>1,998,835</b>	<b>1,998,835</b>	<b>1,601,935</b>	<b>1,302,052</b>
<b>Total In-state Capacity (baseline recycling)</b>	<b>12,398,228</b>	<b>12,820,246</b>	<b>12,897,753</b>	<b>13,177,592</b>	<b>13,298,294</b>	<b>13,462,720</b>	<b>13,630,435</b>	<b>13,404,604</b>	<b>13,279,212</b>
<b>Total In-state Capacity (total recycling)</b>	<b>12,398,228</b>	<b>12,988,186</b>	<b>13,244,548</b>	<b>13,714,717</b>	<b>14,037,809</b>	<b>14,417,297</b>	<b>14,813,387</b>	<b>14,611,215</b>	<b>14,509,954</b>
<b>Net Export (baseline recycling)</b>	<b>1,536,612</b>	<b>1,393,290</b>	<b>1,600,054</b>	<b>1,610,171</b>	<b>1,785,224</b>	<b>1,922,468</b>	<b>2,062,457</b>	<b>2,602,146</b>	<b>3,047,674</b>
<b>Net Export (total recycling)</b>	<b>1,536,612</b>	<b>1,225,351</b>	<b>1,253,259</b>	<b>1,073,046</b>	<b>1,045,709</b>	<b>967,892</b>	<b>879,506</b>	<b>1,395,536</b>	<b>1,816,931</b>

**Assumptions:**

<b>Generation Increase</b>	2.0% (annual)
<b>Baseline Recycling Tonnage Increase</b>	2.0% (annual)
<b>Total Recycling Tonnage Increase</b>	4.5% (annual)
<b>C&amp;D Other Diversion Increase</b>	2.0% (annual)

Combustion Capacity is projected to remain level from 2004 through 2010.

Landfill capacity is calculated to be 81% of total potential based on historical disposal patterns. For 2004, actual landfill disposal is used, which was 73% of permitted capacity.

Net export is calculated by subtracting Total In-State Management Capacity from Total Generation. Total In-State Management

Capacity is the sum of Total Diversion, Combustion Capacity and Potential Landfill Capacity

## **Appendices**

### **Solid Waste Master Plan: 2006 Revision**

**June 2006**

## **Appendices**

**Appendix A - Data Collection and Analysis**

**Appendix B - MSW Management Overview by Municipality**

**Appendix C- Municipal Recycling Tonnages**

**Appendix D - Municipal Recycling Access by Material**

**Appendix E - Disposal Facilities Map**

**Appendix F - Transfer Stations Map**

## **APPENDIX A**

### **Data Collection and Analysis**

This Appendix describes how DEP collects and analyzes solid waste data.

### **Data Collection**

Table A-1 shows the sources DEP relies on to track solid waste data. Each of the data sources is described below.

**Table A-1: Major Solid Waste Data Sources**

<b>Data Type</b>	<b>Data Source</b>
Disposal	<ul style="list-style-type: none"><li>• Annual Facility Reports</li></ul>
Imports / Exports	<ul style="list-style-type: none"><li>• Annual Facility Reports</li><li>• Survey of Other States Data</li></ul>
MSW Recycling	<ul style="list-style-type: none"><li>• Survey of Recycling Processors</li><li>• Survey of Municipalities</li><li>• Bottle Bill Tonnage</li></ul>
Composting	<ul style="list-style-type: none"><li>• Composting Facility Reports</li><li>• Survey of Municipalities</li><li>• Residential Organic Waste Management Study</li></ul>
C&D Recycling	<ul style="list-style-type: none"><li>• Survey of C&amp;D Processors</li></ul>
Other C&D Diversion	<ul style="list-style-type: none"><li>• Annual Facility Reports</li><li>• Survey of C&amp;D Processors</li></ul>

#### *Annual Facility Reports*

In Massachusetts, all landfills, combustion facilities, transfer stations and handling facilities must submit annual reports to DEP summarizing the type and quantity of waste managed. Data from the landfill and combustion facility reports provide information regarding total tonnage of waste disposed in Massachusetts. The reports also contain information on the import and export of waste.

#### *Survey of Other States Data*

In addition to using Annual Facility Reports, DEP gathers information on the import and export of solid waste across state lines by contacting neighboring state solid waste management agencies and significant out-of-state facilities. DEP compares amounts from each of these sources to Massachusetts' data and the largest import/export amount is used.

#### *Municipal Recycling Survey*

Each year, DEP surveys all 351 cities and towns in the Commonwealth to determine the quantity of waste recycled through municipal recycling programs. Recyclables counted are generated by single-family homes and some multi-family residences. The survey also collects data on centralized (off-site) composting of leaf and yard waste that is used to determine the amount of residential composting<sup>1</sup> taking place at municipal and commercial composting facilities. DEP adjusts centralized composting of leaf and yard waste to account for non-reporting towns that operate leaf and yard waste collection programs. DEP does not adjust reported recycling tonnages to account for municipalities who did not report or whose data is incomplete. However, DEP does estimate waste generation for these municipalities. DEP uses a regression analysis based on the towns that do report and multiplies the resulting index of the amount of per capita waste generated (.38 tons per year) by the population of each town lacking generation data.

### *Composting Facility Reports*

Each year, DEP sends a composting survey to all municipal and commercial composting sites. This survey provides the total centralized composting tonnage. To derive a base commercial composting<sup>2</sup> amount, the total amount of residential composting from the municipal recycling survey is subtracted from the total amount reported on the composting facility reports. 100,000 tons is added to the base commercial composting amount to account for farm composting which is not reported to DEP. This figure is an estimate from the Massachusetts Department of Agricultural Resources (DAR).

### *Survey of MSW Recycling Processors*

Each year, DEP surveys all known recycling processors in the state. For known processors that do not respond, their reported tonnages from the previous years are adjusted for average increases or decreases in recycling and carried over. These survey results provide the total statewide MSW recycling tonnage. See below for an explanation of how residential and commercial recycling figures are calculated from this figure.

### *Survey of C&D Processors Survey*

Each year, DEP surveys all known companies that process construction and demolition (C&D) debris for reuse. The companies are surveyed for information on the type and amount of material processed, and the results are used to estimate the C&D recycling rate. DEP attempts to contact all the processors that handle C&D waste. For quantities handled by known processors that do not respond, numbers from the last survey performed are adjusted for increases or decreases in recycling and carried forward.

---

<sup>1</sup> Composting tonnage is considered residential if it originates from a residential source, regardless of where it is composted.

<sup>2</sup> Composting tonnage is considered commercial if it originates from a commercial source, regardless of where it is composted.

### *Bottle Bill Tonnage*

Bottle bill recycling results are credited toward the residential recycling rate. Container recovery (i.e., deposit redemption) rates are obtained from the Massachusetts Department of Revenue. DEP estimates the recycled tonnage using trade association data on both material composition (glass, aluminum, plastic, etc) of the beverage containers recovered and average unit weights for different container types. Composition percentages are adjusted based on information provided by deposit container collection companies to reflect the specific conditions in Massachusetts.

## Data Calculations

The following formulas and definitions are used to estimate quantities in Table 3, Solid Waste Generation and Management, 2000 – 2004. The terms, emphasized in bold type, are presented in the same order in which they appear in the table. Also, completely lower case terms are not included in the table but are calculated in the data analyzed.

**Potential Generation** = Estimated Generation for 2004 based on multiplying 1990 generation by change in Gross State Product from 1990 to 2004. For 2004, Gross State Product figures are not currently available.

**Source Reduction** = Potential Generation – Actual Generation (listed separately for MSW and non-MSW)

**Total Generation** = In-State Disposal + Diversion + Disposal Exports – Disposal Imports

**MSW Generation** = MSW Disposed + MSW Diverted + MSW Exported - MSW Imported

**Residential Generation** = Residential Recycling + Residential Composting + Residential On-site Composting + Bottle Bill + MSW Disposed.

**Commercial Generation** = MSW Generation - Residential Generation

**Non-MSW Generation** = C&D + Other Non-MSW Generation

**C&D Generation** = C&D Disposed + C&D Recycled + C&D Other Diversion + C&D exported – C&D imported

**Other (non-MSW) Generation** = Other Disposed + Other diverted + Other exported – Other imported

**Diversion** = MSW Diversion + Non-MSW Diversion

**MSW Diversion** = Residential Recycling + Commercial Recycling + Residential Off-site Composting + Commercial Composting<sup>3</sup>

**Residential Recycling** is estimated using municipal recycling survey data plus bottle bill data.

**Commercial Recycling** = MSW Recycling (estimated using commercial processors survey and bottle bill data) - Residential Recycling

**Residential Off-site Composting** is estimated using the municipal recycling survey data.

**Commercial Composting** is estimated using composting facility report data – Residential Composting + DAR estimates for farm composting.

**Non-MSW Diversion** = C&D Recycling + C&D Other Diversion

**C&D Recycling** is estimated using data from the C&D processors survey.

**C&D Other Diversion** includes C&D fines used for landfill cover, wood burned as fuel, and C&D residuals used for inactive landfill closures.

---

<sup>3</sup> Residential on-site composting, or home composting, is not counted as part of MSW Diversion, but instead as source reduction.

**Disposal** = Landfill Disposal + Combustion Disposal + Disposal Exports – Disposal Imports

**Disposal Exports** and **Imports** are estimated using data from Annual Facility Reports and a survey of other states.

**Landfill Disposal** = MSW Disposal + C&D Disposal + Other Disposal

**MSW** Disposal is estimated using data from Annual Facility Reports

**C&D** Disposal is estimated using data from Annual Facility Reports

**Other** Disposal is estimated using data from Annual Facility Reports, and represents all non-MSW disposal other than C&D (e.g., contaminated media, recycling residues, industrial waste, street sweepings, etc.)

**Combustion** = MSW Combustion + non-MSW Combustion

**MSW** Combustion is estimated using data from Annual Facility Reports

**Non- MSW** Combustion is estimated using data from Annual Facility Reports



## Methodology Changes

- **Estimation Of Growth Rates For MSW Generation, Recycling And C&D Diversion Rate for Projection Net Export**

The Beyond 2000 Solid Waste Master Plan projected that MSW Generation would increase 1.5% per year until 2006, and then level off, MSW Recycling would increase 1.4% per year, and the Non-MSW Recycling rate would reach a rate of 85% by 2006 and level off. These assumptions were used to project needed landfill capacity in order to meet the no net import/no net export policy by 2006.

In 2003, the policy of no net import/export was lifted and projection scenarios were changed to reflect what would be needed to achieve our 56% recycling goal (best case scenario) and what our net export would be if recycling was essentially flat (worst case scenario). Both Best and Worst Case Scenarios assume Generation tonnage will increase 2% each year. Best Case Scenario assumes MSW and C&D Recycling Tonnage will increase 4.5% each year, and Worst Case Scenario assumes MSW and C&D Recycling will increase 2% each year.

- **Carry Over Of Survey Tonnage**

Each year, DEP surveys recycling processors. In the past, if a facility did not respond to the survey, DEP carried forward the facility's tonnage reported for the previous or most recent year.

In order to get a better estimate of the recycling and composting tonnage for those facilities surveyed that did not respond to the 2004 survey but did respond to the 2003 survey, DEP applied a % change, reflecting the average change in tonnage reported by all processors.

Recycling processors that reported both in 2003 and 2004 showed on average a decrease of 3% in recycled tonnage, C&D processors that reported both in 2003 and 2004 showed on average a increase of 1% in recycling tonnage, and compost facilities reported an decrease of 5%, compared to companies that reported in 2003. DEP applied these averages to companies that reported in 2003 but not in 2004 to generate a more conservative estimate of their 2004 tonnage.

## Appendix B

### MSW Management Overview By Municipality, 2004

Municipality	Estimated Population	MSW Recycled: Glass, Metal, Paper, Plastic and Textiles	MSW Disposed (Actual Reported)	Estimated MSW Generation (does not include compost)*	MSW Generation Rate (does not include compost)*
ABINGTON	15,445	1,162	6,484	7,646	0.50
ACTON	20,331	1,715	10,956	12,671	0.62
ACUSHNET	10,161	0	0	3,861	*0.38
ADAMS	8,809	312	0	3,347	*0.38
AGAWAM	28,528	2,319	12,423	14,742	0.52
ALFORD	425	81	235	316	0.74
AMESBURY	16,450	851	6,863	7,714	0.47
AMHERST	34,874	788	8,540	9,328	0.27
ANDOVER	31,247	4,010	14,992	19,002	0.61
AQUINNAH	209	32	449	481	2.30
ARLINGTON	43,587	5,672	18,404	24,076	0.55
ASHBURNHAM	6,072	0	0	2,307	*0.38
ASHBY	3,000	0	0	1,140	*0.38
ASHFIELD	1,811	301	470	771	0.43
ASHLAND	15,462	1,307	5,182	6,489	0.42
ATHOL	11,299	33	10	43	0.00
ATTLEBORO	41,103	4,604	19,959	24,563	0.60
AUBURN	16,216	813	6,955	7,768	0.48
AVON	4,330	308	2,085	2,393	0.55
AYER	7,287	1,651	2,257	3,908	0.54
BARNSTABLE	47,821	2,827	31,605	34,432	0.72
BARRE	4,847	723	0	1,842	*0.38
BECKET	1,755	191	866	1,057	0.60
BEDFORD	13,272	0	0	5,043	*0.38
BELCHERTOWN	14,300	753	3,653	4,406	0.31
BELLINGHAM	15,314	897	0	5,819	*0.38
BELMONT	24,194	2,822	9,936	12,758	0.53
BERKLEY	6,020	399	1,254	1,653	0.27
BERLIN	2,348	447	1,163	1,610	0.69
BERNARDSTON	2,154	272	597	869	0.40
BEVERLY	40,000	3,089	21,522	24,610	0.62
BILLERICA	39,000	2,646	20,540	23,186	0.59
BLACKSTONE	8,809	487	2,800	3,287	0.37
BLANDFORD	1,259	248	0	478	*0.38
BOLTON	4,716	575	707	1,282	0.27
BOSTON	588,501	26,039	258,065	284,104	0.48
BOURNE	19,606	2,981	8,781	11,762	0.60
BOXBOROUGH	3,452	287	1,509	1,796	0.52
BOXFORD	8,588	1,319	2,355	3,674	0.43
BOYLSTON	4,100	37	0	1,558	*0.38

<b>Municipality</b>	<b>Estimated Population</b>	<b>MSW Recycled: Glass, Metal, Paper, Plastic and Textiles</b>	<b>MSW Disposed (Actual Reported)</b>	<b>Estimated MSW Generation (does not include compost)*</b>	<b>MSW Generation Rate (does not include compost)*</b>
BRAINTREE	33,828	2,206	18,120	20,326	0.60
BREWSTER	9,600	961	6,446	7,407	0.77
BRIDGEWATER	25,185	0	0	9,570	*0.38
BRIMFIELD	3,339	0	0	1,269	*0.38
BROCKTON	95,994	6,072	32,685	38,757	0.40
BROOKFIELD	3,159	348	1,209	1,557	0.49
BROOKLINE	55,407	4,940	24,582	29,522	0.53
BUCKLAND	1,967	183	284	467	0.24
BURLINGTON	22,876	0	0	8,693	*0.38
CAMBRIDGE	101,355	10,089	29,367	39,456	0.39
CANTON	18,725	0	0	7,116	*0.38
CARLISLE	5,400	843	2,342	3,185	0.59
CARVER	11,843	0	0	4,500	*0.38
CHARLEMONT	1,358	100	252	352	0.26
CHARLTON	13,279	0	0	5,046	*0.38
CHATHAM	6,625	1,188	8,492	9,680	1.46
CHELMSFORD	32,780	3,508	15,887	19,395	0.59
CHELSEA	35,080	1,483	14,202	15,684	0.45
CHESHIRE	3,401	268	900	1,168	0.34
CHESTER	1,317	89	482	571	0.43
CHESTERFIELD	1,048	110	177	287	0.27
CHICOPEE	54,653	5,652	19,508	25,160	0.46
CHILMARK	671	112	520	631	0.94
CLARKSBURG	1,800	0	0	684	*0.38
CLINTON	13,593	0	0	5,165	*0.38
COHASSET	7,261	1,455	2,955	4,410	0.61
COLRAIN	1,813	186	248	434	0.24
CONCORD	17,000	2,429	4,387	6,816	0.40
CONWAY	1,809	290	596	886	0.49
CUMMINGTON	802	124	313	437	0.55
DALTON	7,245	433	636	1,069	0.15
DANVERS	24,339	1,599	23,035	24,634	1.01
DARTMOUTH	31,532	2,097	11,224	13,321	0.42
DEDHAM	23,411	1,828	11,303	13,130	0.56
DEERFIELD	4,750	551	2,200	2,751	0.58
DENNIS	15,973	1,595	11,791	13,386	0.84
DIGHTON	6,175	615	1,448	2,063	0.33
DOUGLAS	7,992	312	3,827	4,139	0.52
DOVER	5,986	0	0	2,275	*0.38
DRACUT	29,399	2,058	13,130	15,188	0.52
DUDLEY	10,036	256	4,309	4,565	0.45
DUNSTABLE	2,900	254	1,060	1,314	0.45
DUXBURY	14,403	2,125	7,086	9,211	0.64
EAST BRIDGEWATER	13,526	958	3,743	4,701	0.35

<b>Municipality</b>	<b>Estimated Population</b>	<b>MSW Recycled: Glass, Metal, Paper, Plastic and Textiles</b>	<b>MSW Disposed (Actual Reported)</b>	<b>Estimated MSW Generation (does not include compost)*</b>	<b>MSW Generation Rate (does not include compost)*</b>
EAST BROOKFIELD	2,097	199	590	789	0.38
EAST LONGMEADOW	16,136	1,697	5,187	6,884	0.43
EASTHAM	5,600	1,058	5,094	6,152	1.10
EASTHAMPTON	15,994	0	0	6,078	*0.38
EASTON	23,356	0	0	8,875	*0.38
EDGARTOWN	3,138	1,985	6,200	8,185	2.61
EGREMONT	1,345	290	446	736	0.55
ERVING	1,467	236	575	811	0.55
ESSEX	3,267	365	1,472	1,837	0.56
EVERETT	38,500	899	21,771	22,671	0.59
FAIRHAVEN	16,159	908	6,761	7,669	0.47
FALL RIVER	91,938	2,514	35,634	38,148	0.41
FALMOUTH	35,000	4,252	16,675	20,927	0.60
FITCHBURG	39,000	4,976	21,246	26,222	0.67
FLORIDA	676	84	359	443	0.66
FOXBOROUGH	16,668	1,901	5,887	7,788	0.47
FRAMINGHAM	67,000	5,580	22,826	28,406	0.42
FRANKLIN	28,500	3,385	12,745	16,130	0.57
FREETOWN	9,069	319	4,751	5,070	0.56
GARDNER	20,770	0	0	7,893	*0.38
GEORGETOWN	7,400	0	0	2,812	*0.38
GILL	1,363	138	254	392	0.29
GLOUCESTER	30,273	2,796	12,657	15,453	0.51
GOSHEN	862	89	174	263	0.30
GOSNOLD	96	0	0	36	*0.38
GRAFTON	14,894	0	0	5,660	*0.38
GRANBY	6,132	677	4,772	5,449	0.89
GRANVILLE	1,441	146	292	438	0.30
GREAT BARRINGTON	7,740	198	3,994	4,192	0.54
GREENFIELD	18,168	2,417	6,225	8,642	0.48
GROTON	8,750	869	1,501	2,370	0.27
GROVELAND	6,200	0	0	2,356	*0.38
HADLEY	4,117	0	0	1,564	*0.38
HALIFAX	7,500	688	1,328	2,016	0.27
HAMILTON	8,645	856	3,040	3,896	0.45
HAMPDEN	5,352	212	1,042	1,254	0.23
HANCOCK	721	86	268	354	0.49
HANOVER	13,918	1,864	7,099	8,963	0.64
HANSON	9,366	390	4,464	4,854	0.52
HARDWICK	2,622	174	1,115	1,289	0.49
HARVARD	5,335	811	2,601	3,412	0.64
HARWICH	11,200	1,811	7,818	9,629	0.86
HATFIELD	3,224	291	348	638	0.20
HAVERHILL	58,969	3,141	37,100	40,241	0.68

<b>Municipality</b>	<b>Estimated Population</b>	<b>MSW Recycled: Glass, Metal, Paper, Plastic and Textiles</b>	<b>MSW Disposed (Actual Reported)</b>	<b>Estimated MSW Generation (does not include compost)*</b>	<b>MSW Generation Rate (does not include compost)*</b>
HAWLEY	336	40	0	128	*0.38
HEATH	805	108	252	360	0.45
HINGHAM	20,385	2,292	9,890	12,182	0.60
HINSDALE	1,872	173	378	551	0.29
HOLBROOK	10,785	789	3,750	4,538	0.42
HOLDEN	15,082	1,090	7,258	8,348	0.55
HOLLAND	2,280	0	0	866	*0.38
HOLLISTON	13,801	0	0	5,244	*0.38
HOLYOKE	39,838	1,778	0	15,138	*0.38
HOPEDALE	6,000	776	2,064	2,840	0.47
HOPKINTON	14,463	1,509	5,248	6,757	0.47
HUBBARDSTON	4,218	0	0	1,603	*0.38
HUDSON	17,770	0	0	6,753	*0.38
HULL	11,050	0	0	4,199	*0.38
HUNTINGTON	2,120	203	538	740	0.35
IPSWICH	13,460	1,486	5,121	6,607	0.49
KINGSTON	10,227	806	5,328	6,134	0.60
LAKEVILLE	10,129	859	3,269	4,128	0.41
LANCASTER	6,030	0	0	2,291	*0.38
LANESBOROUGH	2,990	0	0	1,136	*0.38
LAWRENCE	72,043	2,381	39,144	41,525	0.58
LEE	6,247	396	0	2,374	*0.38
LEICESTER	10,731	0	0	4,078	*0.38
LENOX	5,077	337	0	1,929	*0.38
LEOMINSTER	41,303	2,270	14,366	16,636	0.40
LEVERETT	2,019	209	227	436	0.22
LEXINGTON	31,507	0	0	11,973	*0.38
LEYDEN	683	0	0	260	*0.38
LINCOLN	5,661	732	1,095	1,827	0.32
LITTLETON	8,225	802	4,781	5,583	0.68
LONGMEADOW	15,032	1,973	5,510	7,483	0.50
LOWELL	105,167	4,148	67,886	72,034	0.68
LUDLOW	20,714	1,256	8,480	9,736	0.47
LUNENBURG	9,439	587	1,480	2,067	0.22
LYNN	89,050	1,735	54,373	56,108	0.63
LYNNFIELD	12,000	1,015	5,583	6,599	0.55
MALDEN	56,000	0	24,000	21,280	*0.38
MANCHESTER	5,228	810	2,231	3,041	0.58
MANSFIELD	22,700	2,787	7,170	9,957	0.44
MARBLEHEAD	20,255	0	0	7,697	*0.38
MARION	5,694	457	2,178	2,635	0.46
MARLBOROUGH	38,500	2,267	15,418	17,685	0.46
MARSHFIELD	24,324	2,784	14,593	17,377	0.71
MASHPEE	12,946	1,150	6,692	7,842	0.61

<b>Municipality</b>	<b>Estimated Population</b>	<b>MSW Recycled: Glass, Metal, Paper, Plastic and Textiles</b>	<b>MSW Disposed (Actual Reported)</b>	<b>Estimated MSW Generation (does not include compost)*</b>	<b>MSW Generation Rate (does not include compost)*</b>
MATTAPOISETT	5,955	0	0	2,263	*0.38
MAYNARD	10,370	1,330	2,236	3,566	0.34
MEDFIELD	12,944	1,084	3,854	4,938	0.38
MEDFORD	55,765	5,360	31,674	37,034	0.66
MEDWAY	12,800	1,727	4,708	6,435	0.50
MELROSE	27,114	2,189	10,135	12,324	0.45
MENDON	6,143	389	1,898	2,286	0.37
MERRIMAC	6,138	426	1,387	1,813	0.30
METHUEN	41,731	3,079	21,449	24,528	0.59
MIDDLEBOROUGH	19,622	862	8,772	9,634	0.49
MIDDLEFIELD	394	55	166	221	0.56
MIDDLETON	7,744	603	2,356	2,959	0.38
MILFORD	26,617	2,176	7,981	10,157	0.38
MILLBURY	12,228	0	0	4,647	*0.38
MILLIS	8,100	0	1,172	3,078	*0.38
MILLVILLE	3,000	0	0	1,140	*0.38
MILTON	26,000	4,202	6,079	10,280	0.40
MONROE	114	0	0	43	*0.38
MONSON	8,300	565	3,532	4,097	0.49
MONTAGUE	8,492	967	1,304	2,271	0.27
MONTEREY	940	0	0	357	*0.38
MONTGOMERY	801	0	0	304	*0.38
MOUNT WASHINGTON	135	0	38	51	*0.38
NAHANT	3,691	292	2,529	2,822	0.76
NANTUCKET	6,600	0	0	2,508	*0.38
NATICK	32,170	3,132	8,837	11,969	0.37
NEEDHAM	29,156	5,381	10,891	16,272	0.56
NEW ASHFORD	247	0	0	94	*0.38
NEW BEDFORD	99,922	3,149	44,170	47,319	0.47
NEW BRAINTREE	926	0	0	352	*0.38
NEW MARLBOROUGH	1,494	123	1,274	1,398	0.94
NEW SALEM	929	109	198	307	0.33
NEWBURY	6,717	549	2,716	3,265	0.49
NEWBURYPORT	17,189	1,909	7,935	9,844	0.57
NEWTON	81,179	11,673	34,363	46,036	0.57
NORFOLK	9,270	782	2,232	3,014	0.33
NORTH ADAMS	15,038	0	0	5,714	*0.38
NORTH ANDOVER	24,279	2,140	12,612	14,752	0.61
NORTH ATTLEBOROUGH	27,291	2,714	12,981	15,695	0.58
NORTH BROOKFIELD	4,742	335	1,047	1,382	0.29
NORTH READING	13,737	901	6,631	7,533	0.55
NORTHAMPTON	30,842	3,480	4,363	7,842	0.25
NORTHBOROUGH	14,129	1,726	3,865	5,591	0.40
NORTHBRIDGE	13,988	684	7,346	8,030	0.57

<b>Municipality</b>	<b>Estimated Population</b>	<b>MSW Recycled: Glass, Metal, Paper, Plastic and Textiles</b>	<b>MSW Disposed (Actual Reported)</b>	<b>Estimated MSW Generation (does not include compost)*</b>	<b>MSW Generation Rate (does not include compost)*</b>
NORTHFIELD	2,951	393	845	1,238	0.42
NORTON	18,036	0	0	6,854	*0.38
NORWELL	9,765	1,115	4,193	5,308	0.54
NORWOOD	28,326	0	0	10,764	*0.38
OAK BLUFFS	4,159	378	1,075	1,454	0.35
OAKHAM	1,689	0	0	642	*0.38
ORANGE	7,518	434	3,154	3,588	0.48
ORLEANS	6,827	0	0	2,594	*0.38
OTIS	1,122	293	902	1,195	1.07
OXFORD	14,200	425	8,345	8,770	0.62
PALMER	12,475	1,320	0	4,741	*0.38
PAXTON	6,000	0	0	2,280	*0.38
PEABODY	48,129	2,996	26,620	29,616	0.62
PELHAM	1,430	84	308	392	0.27
PEMBROKE	16,974	0	0	6,450	*0.38
PEPPERELL	11,115	708	0	4,224	*0.38
PERU	821	45	259	304	0.37
PETERSHAM	1,177	72	342	414	0.35
PHILLIPSTON	1,667	0	0	633	*0.38
PITTSFIELD	47,927	3,228	17,625	20,853	0.44
PLAINFIELD	609	79	97	176	0.29
PLAINVILLE	7,229	722	2,562	3,284	0.45
PLYMOUTH	49,008	4,046	28,699	32,745	0.67
PLYMPTON	2,785	0	0	1,058	*0.38
PRINCETON	3,531	0	0	1,342	*0.38
PROVINCETOWN	3,577	1,029	4,575	5,604	1.57
QUINCY	85,988	36,050	45,385	81,435	0.95
RANDOLPH	31,365	1,617	14,978	16,595	0.53
RAYNHAM	11,739	827	3,799	4,626	0.39
READING	23,708	1,941	9,690	11,631	0.49
REHOBOTH	10,007	0	0	3,803	*0.38
REVERE	43,766	1,357	25,552	26,909	0.61
RICHMOND	1,604	206	623	829	0.52
ROCHESTER	5,076	228	2,443	2,671	0.53
ROCKLAND	16,559	1,376	6,155	7,531	0.45
ROCKPORT	7,300	1,124	6,111	7,235	0.99
ROWE	351	79	224	303	0.86
ROWLEY	5,300	276	0	2,014	*0.38
ROYALSTON	1,213	416	254	669	0.55
RUSSELL	1,704	136	335	471	0.28
RUTLAND	5,303	0	0	2,015	*0.38
SALEM	40,407	2,572	17,750	20,322	0.50
SALISBURY	7,200	53	0	2,736	*0.38
SANDISFIELD	824	0	0	313	*0.38

<b>Municipality</b>	<b>Estimated Population</b>	<b>MSW Recycled: Glass, Metal, Paper, Plastic and Textiles</b>	<b>MSW Disposed (Actual Reported)</b>	<b>Estimated MSW Generation (does not include compost)*</b>	<b>MSW Generation Rate (does not include compost)*</b>
SANDWICH	20,500	1,479	10,145	11,624	0.57
SAUGUS	25,553	1,752	12,529	14,281	0.56
SAVOY	705	41	125	166	0.24
SCITUATE	18,000	2,689	7,391	10,080	0.56
SEEKONK	13,425	1,749	3,375	5,125	0.38
SHARON	17,739	2,027	9,258	11,285	0.64
SHEFFIELD	3,350	411	853	1,264	0.38
SHELBURNE	2,058	203	468	671	0.33
SHERBORN	4,552	920	1,932	2,852	0.63
SHIRLEY	5,200	0	0	1,976	*0.38
SHREWSBURY	31,060	0	0	11,803	*0.38
SHUTESBURY	1,807	193	430	623	0.34
SOMERSET	18,234	1,703	5,383	7,087	0.39
SOMERVILLE	80,000	4,293	36,117	40,410	0.51
SOUTH HADLEY	15,463	1,733	4,563	6,296	0.41
SOUTHAMPTON	5,474	1,071	1,046	2,117	0.39
SOUTHBOROUGH	9,600	1,191	5,341	6,533	0.68
SOUTHBRIDGE	17,000	0	0	6,460	*0.38
SOUTHWICK	8,000	700	2,625	3,325	0.42
SPENCER	11,691	958	4,633	5,591	0.48
SPRINGFIELD	150,000	6,264	68,014	74,278	0.50
STERLING	7,445	974	2,378	3,352	0.45
STOCKBRIDGE	2,397	992	2,410	3,402	1.42
STONEHAM	22,238	1,930	9,881	11,811	0.53
STOUGHTON	27,147	1,222	10,755	11,977	0.44
STOW	5,626	0	0	2,138	*0.38
STURBRIDGE	8,057	449	315	764	0.09
SUDBURY	16,929	846	2,476	3,322	0.20
SUNDERLAND	3,777	270	690	960	0.25
SUTTON	8,100	908	4,068	4,976	0.61
SWAMPSCOTT	14,412	1,275	5,661	6,936	0.48
SWANSEA	15,901	0	0	6,042	*0.38
TAUNTON	55,976	3,865	19,217	23,082	0.41
TEMPLETON	6,600	450	2,671	3,121	0.47
TEWKSBURY	29,077	1,533	13,345	14,878	0.51
TISBURY	3,102	512	1,372	1,884	0.61
TOLLAND	326	0	0	124	*0.38
TOPSFIELD	6,327	887	2,126	3,013	0.48
TOWNSEND	9,501	917	3,292	4,209	0.44
TRURO	1,821	394	2,071	2,465	1.35
TYNGSBOROUGH	11,081	1,143	5,315	6,458	0.58
TYRINGHAM	363	59	159	218	0.60
UPTON	7,028	715	2,266	2,981	0.42
UXBRIDGE	12,000	830	5,605	6,435	0.54



<b>Municipality</b>	<b>Estimated Population</b>	<b>MSW Recycled: Glass, Metal, Paper, Plastic and Textiles</b>	<b>MSW Disposed (Actual Reported)</b>	<b>Estimated MSW Generation (does not include compost)*</b>	<b>MSW Generation Rate (does not include compost)*</b>
WAKEFIELD	24,741	1,807	10,652	12,459	0.50
WALES	1,440	78	274	352	0.24
WALPOLE	23,225	2,102	9,448	11,550	0.50
WALTHAM	59,229	3,895	25,326	29,221	0.49
WARE	10,254	0	0	3,897	*0.38
WAREHAM	23,200	264	12,661	12,925	0.56
WARREN	4,850	0	0	1,843	*0.38
WARWICK	750	107	194	301	0.40
WASHINGTON	615	0	0	234	*0.38
WATERTOWN	32,986	2,710	14,391	17,101	0.52
WAYLAND	13,915	2,166	4,437	6,603	0.47
WEBSTER	15,700	0	0	5,966	*0.38
WELLESLEY	26,215	3,311	15,465	18,776	0.72
WELLFLEET	3,128	918	3,142	4,060	1.30
WENDELL	986	137	224	361	0.37
WENHAM	4,473	0	1,500	1,700	*0.38
WEST BOYLSTON	6,823	555	2,082	2,636	0.39
WEST BRIDGEWATER	6,694	373	2,991	3,364	0.50
WEST BROOKFIELD	3,707	0	0	1,409	*0.38
WEST NEWBURY	4,262	683	2,076	2,759	0.65
WEST SPRINGFIELD	28,000	1,927	12,289	14,215	0.51
WEST STOCKBRIDGE	1,502	154	475	629	0.42
WEST TISBURY	2,335	120	804	924	0.40
WESTBOROUGH	17,997	1,402	9,576	10,978	0.61
WESTFIELD	39,310	4,206	16,611	20,817	0.53
WESTFORD	21,610	2,759	9,034	11,793	0.55
WESTHAMPTON	1,374	173	363	535	0.39
WESTMINSTER	6,477	490	0	2,461	*0.38
WESTON	10,660	1,097	5,024	6,121	0.57
WESTPORT	14,584	901	6,039	6,940	0.48
WESTWOOD	14,774	1,880	6,065	7,945	0.54
WEYMOUTH	54,207	3,211	34,692	37,903	0.70
WHATELY	1,573	147	200	347	0.22
WHITMAN	13,416	0	0	5,098	*0.38
WILBRAHAM	14,449	1,461	2,934	4,395	0.30
WILLIAMSBURG	2,559	356	716	1,072	0.42
WILLIAMSTOWN	8,424	513	1,057	1,570	0.19
WILMINGTON	21,094	1,822	10,914	12,736	0.60
WINCHENDON	9,654	718	1,670	2,388	0.25
WINCHESTER	20,044	1,840	9,713	11,553	0.58
WINDSOR	875	104	154	258	0.29
WINTHROP	18,303	1,586	5,640	7,226	0.39
WOBURN	37,500	2,284	21,197	23,481	0.63
WORCESTER	172,648	10,304	33,768	44,072	0.26

<b>Municipality</b>	<b>Estimated Population</b>	<b>MSW Recycled: Glass, Metal, Paper, Plastic and Textiles</b>	<b>MSW Disposed (Actual Reported)</b>	<b>Estimated MSW Generation (does not include compost)*</b>	<b>MSW Generation Rate (does not include compost)*</b>
WORTHINGTON	1,248	184	335	520	0.42
WRENTHAM	10,160	1,510	3,812	5,322	0.52
YARMOUTH	22,600	2,765	15,756	18,521	0.82
<b>TOTALS: 351</b>	<b>6,354,147</b>	<b>460,904</b>	<b>2,432,607</b>	<b>3,175,289</b>	
*Default estimated generation rate is		0.38			

**APPENDIX C**  
**2004 Municipal Recycling Tonnages for Major Material Types**

Municipality	Aluminum	Cardboard	Commingled Containers	Glass	Mixed Paper	Newspaper	Plastic Containers	Scrap Metal/ White Goods	Steel/Tin cans	Textiles/ Used Clothing
ABINGTON			253			909				
ACTON			312			1,043		360		
ACUSHNET										
ADAMS			69		231			12		
AGAWAM			700		1,455			164		
ALFORD			27		54					
AMESBURY			851							
AMHERST			127		516			134		11
ANDOVER			698		3,002			290		20
ARLINGTON			1,058		3,827			787		1
ASHBURNHAM										
ASHBY										
ASHFIELD			87		161			39		14
ASHLAND		48	285		970			4		
ATHOL								30		3
ATTLEBORO			848		1,917			1,840		
AUBURN			215			599				
AVON			58		221			29		
AYER	3	74	1,065	40	134	100	46	178	11	
BARNSTABLE	39	402		300	307	777	67	801	50	84
BARRE			80		226			412		5
BECKET			33		81			77		
BEDFORD										
BELCHERTOWN			118		497		27	112		
BELLINGHAM	25	20		7	100	370	115		255	5
BELMONT			693		2,042			87		
BERKLEY	0	59		27	71	92	20	116		15
BERLIN		60	22		31	108		216		10
BERNARDSTON			57		130			85		
BEVERLY			618		2,363			108		
BILLERICA			635			1,704		307		
BLACKSTONE		6	148			325		7		1

Municipality	Aluminum	Cardboard	Commingled Containers	Glass	Mixed Paper	Newspaper	Plastic Containers	Scrap Metal/ White Goods	Steel/Tin cans	Textiles/ Used Clothing
BLANDFORD			215		33					
BOLTON		159	38	63	139	104		47		25
BOSTON			4,600		15,122			5,850		467
BOURNE	35	420		214	26	1,127	82	975	73	29
BOXBOROUGH		9		27	247				4	
BOXFORD		37	338		865			77		2
BOYLSTON			8			29				
BRAINTREE	0		537		1,658			3		8
BREWSTER				138	580		72	121		50
BRIDGEWATER			215		681			60		28
BRIMFIELD										
BROCKTON			1,402		4,115			550		5
BROOKFIELD	4	36		15	45	52	20	160	6	10
BROOKLINE			1,030		3,684			226		
BUCKLAND			51		101			31		
BURLINGTON										
CAMBRIDGE		105	3,373		6,354		20	151		86
CANTON										
CARLISLE		139		94	230	204	36	130	10	
CARVER										
CHARLEMONT			39		61					
CHARLTON										
CHATHAM		177		246	22	311	26	330	27	49
CHELMSFORD		129	839		2,356			55		129
CHELSEA			500					983		
CHESHIRE		44			148			76		
CHESTER			24		65					
CHESTERFIELD			23		65			15		7
CHICOPEE			1,003		3,616			1,033		
CHILMARK			17	8		50		10		27
CLARKSBURG										
CLINTON										
COHASSET		232		133	690		45	247	23	85
COLRAIN			49		92			45		
CONCORD		85	426		1,562			26		330
CONWAY			72		165			53		
CUMMINGTON			30		77			14		4

Municipality	Aluminum	Cardboard	Commingled Containers	Glass	Mixed Paper	Newspaper	Plastic Containers	Scrap Metal/ White Goods	Steel/Tin cans	Textiles/ Used Clothing
DALTON			84		329			20		
DANVERS			310		1,108			172		9
DARTMOUTH		185	381	21	253	940	10	284	5	18
DEDHAM			497		1,160			170		
DEERFIELD			130		341			80		
DENNIS		226		144	133	470	32	411	23	156
DIGHTON			184		371			60		
DOUGLAS				25	178		15	87	7	
DOVER										
DRACUT			459		1,191			339		69
DUDLEY		39		25		116	11	55	10	
DUNSTABLE	3	34		39	136		20	20	2	
DUXBURY		423		214		853	59	476		100
EAST BRIDGEWATER			247		711					
EAST BROOKFIELD			47		133			19		
EAST LONGMEADOW			430		1,192			75		
EASTHAM		133	12	123	146	297	24	265	18	40
EASTHAMPTON										
EASTON										
EDGARTOWN		290	196	275	100	394	20	405	29	275
EGREMONT			77		148			63		1
ERVING			68		123			45		
ESSEX		20	56		160			117		12
EVERETT			229			670				
FAIRHAVEN		298			515			55		40
FALL RIVER			821		1,443			249		1
FALMOUTH		182	872		2,098			1,075		25
FITCHBURG		73	322		790	97		3,304	391	
FLORIDA			17		40			27		
FOXBOROUGH			367		1,299			235		
FRAMINGHAM		138	1,187	15	3,929			302	3	6
FRANKLIN			689		2,282			410		4
FREETOWN		43		23		92		147	9	5
GARDNER										
AQUINNAH		6	8			18				
GEORGETOWN										
GILL			50		88					

Municipality	Aluminum	Cardboard	Commingled Containers	Glass	Mixed Paper	Newspaper	Plastic Containers	Scrap Metal/ White Goods	Steel/Tin cans	Textiles/ Used Clothing
GLOUCESTER			677		1,804			175		140
GOSHEN			23		49			13		4
GOSNOLD										
GRAFTON										
GRANBY			86		307	5		279		
GRANVILLE			31		84			30		
GREAT BARRINGTON			30		108			60		1
GREENFIELD		130	403		1,189	142		553		
GROTON	4	122		131	419		43	107	19	24
GROVELAND										
HADLEY										
HALIFAX		42	79		37	137	13	102	277	1
HAMILTON		11	203		440			202		
HAMPDEN		44	49		59	45		15		
HANCOCK			15		37			34		
HANOVER	13	266		98		758	50	550	14	114
HANSON			45			158		164	17	6
HARDWICK		24	35		108			1		6
HARVARD		72		171	68	289	35	156	20	
HARWICH		199		150	76	468	43	767	28	80
HATFIELD			61		166			46		17
HAVERHILL	7			92	2,815		12	200	15	
HAWLEY			14		26					
HEATH			25		42			41		
HINGHAM		197	39	333	1,160		75	458		30
HINSDALE			36		92			45		
HOLBROOK		163				564			61	
HOLDEN			315		775					
HOLLAND										
HOLLISTON										
HOLYOKE		18	323		1,178			259		
HOPEDALE		225	134		333			15		70
HOPKINTON			382		1,127					
HUBBARDSTON										
HUDSON										
HULL										
HUNTINGTON			51		120			32		

Municipality	Aluminum	Cardboard	Commingled Containers	Glass	Mixed Paper	Newspaper	Plastic Containers	Scrap Metal/ White Goods	Steel/Tin cans	Textiles/ Used Clothing
IPSWICH			346		1,126			14		
KINGSTON		35	92			315		352		12
LAKEVILLE		164	110	57	126	194	34	99	26	48
LANCASTER										
LANESBOROUGH										
LAWRENCE		741	255		871			514		
LEE			121		275					
LEICESTER										
LENOX			103		234					
LEOMINSTER		47	347		1,166	104		468		138
LEVERETT		8	57		127			14		3
LEXINGTON										
LEYDEN										
LINCOLN				53	492		15	118	55	
LITTLETON				74	470		38	174	19	27
LONGMEADOW			405		1,375			189		4
LOWELL			990		2,482			548		128
LUDLOW			308		808			140		
LUNENBURG			188		399					
LYNN			205		1,530					
LYNNFIELD			231		725			47		12
MALDEN										
MANCHESTER			204		511			95		
MANSFIELD			580	26	1,638		15	483	8	37
MARBLEHEAD										
MARION			95			214		148		
MARLBOROUGH			576		1,509			172		10
MARSHFIELD			547		1,683			549		5
MASHPEE		273		92	175	292	24	281	13	
MATTAPOISETT										
MAYNARD		50	285			892		103		
MEDFIELD				40	923		20	81	20	
MEDFORD			620			2,346		2,394		
MEDWAY			373		1,149			205		
MELROSE		52	370		1,578			167		22
MENDON			273						116	
MERRIMAC			115		311					

Municipality	Aluminum	Cardboard	Commingled Containers	Glass	Mixed Paper	Newspaper	Plastic Containers	Scrap Metal/ White Goods	Steel/Tin cans	Textiles/ Used Clothing
METHUEN			388		2,271			413		7
MIDDLEBOROUGH		35	48		9	380		387		3
MIDDLEFIELD			14		26			12		4
MIDDLETON				43	344		29	121	9	57
MILFORD			417		1,178			557		24
MILLBURY										
MILLIS										
MILLVILLE										
MILTON			979		2,998			138		86
MONROE										
MONSON			145			399		20		
MONTAGUE			232		601			134		
MONTEREY										
MONTGOMERY										
MOUNT WASHINGTON										
NAHANT			63			190		39		
NANTUCKET										
NATICK			765		2,368					
NEEDHAM		164	832		3,356			832		197
NEW ASHFORD										
NEW BEDFORD		275	540		197	1,332		772		33
NEW BRAINTREE										
NEW MARLBOROUGH			32		56			35		
NEW SALEM			28		68			13		
NEWBURY			126		318			105		
NEWBURYPORT			482		1,397					30
NEWTON			2,208		8,756			287		422
NORFOLK		133		53	129	226	67	133	12	29
NORTH ADAMS										
NORTH ANDOVER		73	360		1,465			234		8
NORTH ATTLEBOROUGH			750			1,850		114		
NORTH BROOKFIELD	5			26	123	83	8	60	10	20
NORTH READING			215		646			40		
NORTHAMPTON			1,097		1,739			528		115
NORTHBOROUGH			428		1,298					
NORTHBRIDGE			244		440					



Municipality	Aluminum	Cardboard	Commingled Containers	Glass	Mixed Paper	Newspaper	Plastic Containers	Scrap Metal/ White Goods	Steel/Tin cans	Textiles/ Used Clothing
NORTHFIELD			95		213			85		
NORTON										
NORWELL			225		796			94		
NORWOOD										
OAK BLUFFS		146	122			111				
OAKHAM										
ORANGE			91		254			77		12
ORLEANS										
OTIS			58		133			102		
OXFORD	7		17	41	290		8	54	8	
PALMER		120	1,200							
PAXTON										
PEABODY			566			1,976		454		
PELHAM			16		67					
PEMBROKE										
PEPPERELL	12	120		96		151	33	175	21	100
PERU			15		30					
PETERSHAM			17		55					
PHILLIPSTON										
PITTSFIELD			818		2,410					
PLAINFIELD			22		41			13		4
PLAINVILLE			209		489			24		
PLYMOUTH		1,062	285		263	624		687		1,125
PLYMPTON										
PRINCETON										
PROVINCETOWN		357		253		228	22	145	24	
QUINCY	143	469	310	135	1,750	20,100	611		124	4
RANDOLPH			289		1,199			129		
RAYNHAM	4	101		43	129	192	39	267	52	
READING			446		1,427			68		
REHOBOTH										
REVERE			317		970			70		
RICHMOND			55		137			14		
ROCHESTER		5	73			150				
ROCKLAND	3		332	9	838	90	1	102		1
ROCKPORT				113	700		47	122	71	71
ROWE			16		33			30		

Municipality	Aluminum	Cardboard	Commingled Containers	Glass	Mixed Paper	Newspaper	Plastic Containers	Scrap Metal/ White Goods	Steel/Tin cans	Textiles/ Used Clothing
ROWLEY			44		231					
ROYALSTON			37		309			60		10
RUSSELL			33		72			31		
RUTLAND										
SALEM			449		1,473			650		
SALISBURY			20			33				
SANDISFIELD										
SANDWICH		168		116	355		63	711		66
SAUGUS			252		1,500					
SAVOY			12		29					
SCITUATE			491		892	926		240	135	5
SEEKONK			400		1,217			28		104
SHARON			1,948					79		
SHEFFIELD			110		201			100		
SHELBURNE			55		125			23		
SHERBORN			179		627			99		15
SHIRLEY										
SHREWSBURY										
SHUTESBURY			48		137			8		0
SOMERSET			1,588					115		
SOMERVILLE			1,303		2,991					
SOUTH HADLEY			421		1,178			106		28
SOUTHAMPTON			189		486			389		7
SOUTHBOROUGH	0		336			499		279	0	77
SOUTHBRIDGE										
SOUTHWICK			105		355			240		
SPENCER				46	502		75	209	21	105
SPRINGFIELD			1,474		4,040			750		
STERLING		136	206		487			140		5
STOCKBRIDGE			445		495			53		
STONEHAM			781		713			336		100
STOUGHTON		7	361			610		244		
STOW										
STURBRIDGE	4	71		47	104	122	18	61	14	8
SUDBURY		118		86	209	219	39	156		19
SUNDERLAND			75		177			18		
SUTTON		180		29	146		20	525	8	

Municipality	Aluminum	Cardboard	Commingled Containers	Glass	Mixed Paper	Newspaper	Plastic Containers	Scrap Metal/ White Goods	Steel/Tin cans	Textiles/ Used Clothing
SWAMPSCOTT			261		889			125		
SWANSEA										
TAUNTON			1,054			2,611		200		
TEMPLETON		25	145		280					
TEWKSBURY			389		1,019			125		
TISBURY		109	284			49		67		3
TOLLAND										
TOPSFIELD			225		624			38		
TOWNSEND			293		598			26		
TRURO		52		97	107		10	117	11	
TYNGSBOROUGH			347		750			46		
TYRINGHAM			20		39					
UPTON			230		459			16		10
UXBRIDGE			131	4	487				208	
WAKEFIELD			365		1,289			153		
WALES			18		45			16		
WALPOLE			418		1,674					10
WALTHAM		33	873		2,699			290		
WARE										
WAREHAM		19	71			161		13		
WARREN										
WARWICK			26		47			34		
WASHINGTON										
WATERTOWN		879	621	6	12	1,043		149		
WAYLAND		211	150	130	1,177		10	290		199
WEBSTER										
WELLESLEY		464				2,073	84	485	39	166
WELLFLEET		72		125	3	136	136	420	21	5
WENDELL			35		62			40		
WENHAM										
WEST BOYLSTON			130		425					
WEST BRIDGEWATER		81	75			177		30		10
WEST BROOKFIELD										
WEST NEWBURY			191			354		138		
WEST SPRINGFIELD			416		1,192			318		
WEST STOCKBRIDGE			43		102			8		
WEST TISBURY		19	12	17		46		26		

Municipality	Aluminum	Cardboard	Commingled Containers	Glass	Mixed Paper	Newspaper	Plastic Containers	Scrap Metal/ White Goods	Steel/Tin cans	Textiles/ Used Clothing
WESTBOROUGH		147	52	73	13	566		450		100
WESTFIELD			919		2,684			603		
WESTFORD			620		1,925			213		
WESTHAMPTON			65		108					
WESTMINSTER		69	41			97		276		8
WESTON				125	288	498	51	124		11
WESTPORT		109	147	50	106	198	33	161	80	17
WESTWOOD			347			1,460		73		
WEYMOUTH			731			2,324		156		
WHATELY			36		106			5		
WHITMAN										
WILBRAHAM			218		951		48	243		1
WILLIAMSBURG			81		198			61		15
WILLIAMSTOWN			106		331			76		
WILMINGTON			322		1,086			414		
WINCHENDON	17	63		90	148	84	46	236	25	9
WINCHESTER			101	231	1,179			237		92
WINDSOR			21		63			19		
WINTHROP			352		360	860		14		
WOBURN			525		1,412			347		
WORCESTER			2,809		7,217			273		5
WORTHINGTON			44		95			33		12
WRENTHAM			349		1,040			121		
YARMOUTH		338	370		928			995		133
<b>TOTALS</b>	<b>329</b>	<b>13,643</b>	<b>84,902</b>	<b>5,618</b>	<b>211,113</b>	<b>62,001</b>	<b>2,680</b>	<b>59,725</b>	<b>2,557</b>	<b>6,916</b>



## APPENDIX D

### Available Municipal Recycling Access by Material

#### *Recycling Collection Method and Materials Accepted*

Municipality	Collection Method	Leaves/Yard Waste	Christmas Trees	Food/kitchen scraps	Newspaper	Magazines	Junk Mail	White Paper	Cardboard	Paperboard	Phonebooks	Waxed cartons	Aseptic cartons	Clear glass	Brown Glass	Green Glass	Glass	#1 (PET) plastic	#2 (HDPE) plastic	Aluminum cans	Steel/Tin	Aerosol cans	White Goods	Scrap Metal	C&D debris	Textiles	Swap Shop
ABINGTON	curb	X			X	X	X	X	X	X	X	X		X	X	X	X	X	X	X	X		X	X			
ACTON	drop	X	X		X	X	X	X	X		X			X	X	X	X	X	X	X	X		X	X			
ACUSHNET	curb	X	X		X	X	X	X	X	X	X			X	X	X	X	X	X	X	X		X	X			
ADAMS	drop	X	X		X	X	X	X	X	X	X	X	X	X	X	X	X	X	X	X	X						
AGAWAM	curb	X	X		X	X	X	X	X	X	X			X	X	X	X	X	X	X	X		X	X			
ALFORD	drop				X	X	X	X	X	X	X	X	X	X	X	X	X	X	X	X	X	X	X	X	X		
AMESBURY	curb	X	X		X	X	X	X	X	X	X			X	X	X	X		X	X	X						
AMHERST	curb	X	X		X	X	X	X	X	X	X	X	X	X	X	X	X	X	X	X	X	X	X	X	X	X	X
ANDOVER	curb	X			X	X	X	X	X	X	X			X	X	X	X	X	X	X	X			X		X	
AQUINNAH	curb	X	X		X	X	X	X	X	X	X			X	X	X	X	X	X	X	X	X	X	X	X	X	X
ARLINGTON	sub	X	X		X	X	X	X	X	X	X			X	X	X	X	X	X	X	X	X	X	X		X	
ASHBURNHAM	curb	X			X	X	X	X	X		X			X	X	X		X	X	X	X	X	X	X	X		
ASHBY	drop				X	X	X	X	X	X				X	X	X	X	X	X	X	X			X			
ASHFIELD	curb				X	X	X	X	X	X	X	X	X	X	X	X	X	X	X	X	X	X	X	X		X	X
ASHLAND	sub	X	X		X	X	X	X	X	X	X			X	X	X	X			X	X		X				
ATHOL	curb				X	X	X	X	X	X	X	X	X	X	X	X	X	X	X	X	X		X	X		X	
ATTLEBORO	curb	X	X		X	X	X	X	X	X	X			X	X	X	X	X	X	X	X	X	X	X			
AUBURN	curb	X	X		X	X	X	X	X		X		X	X	X	X		X	X	X	X		X				
AVON	drop	X	X		X	X	X	X	X	X	X			X	X	X	X	X	X	X	X		X				
AYER	drop	X	X		X	X	X	X	X	X	X			X	X	X	X	X	X	X	X		X	X		X	X
BARNSTABLE	drop	X	X	X	X	X	X	X	X	X	X			X	X	X		X	X	X	X	X	X	X	X	X	X
BARRE	drop	X	X		X	X	X	X	X	X	X		X	X	X	X	X	X	X	X	X	X	X	X	X	X	X
BECKET	curb				X	X	X	X	X	X	X	X	X	X	X	X	X	X	X	X	X		X	X			
BEDFORD	drop	X			X	X	X	X	X	X	X			X	X	X		X	X	X	X		X	X			
BELCHERTOWN	curb	X	X		X	X	X	X	X	X	X			X	X	X	X	X	X	X	X		X	X		X	
BELLINGHAM	curb	X	X	X	X	X	X	X	X	X	X			X	X	X	X	X	X	X	X	X		X			
BELMONT	drop	X			X	X	X	X		X	X	X		X	X	X	X	X	X	X	X		X				
BERKLEY	drop	X	X		X	X	X	X	X	X	X			X	X	X		X	X	X	X	X	X	X	X	X	X
BERLIN	drop		X		X	X	X	X	X					X	X	X	X	X	X	X	X		X	X		X	X
BERNARDSTON	curb				X	X	X	X	X	X	X	X	X	X	X	X	X	X	X	X	X	X	X	X	X		X
BEVERLY	curb	X			X	X	X	X	X	X	X	X		X	X	X	X	X	X	X	X	X	X				
BILLERICA	curb	X			X	X	X	X	X		X			X	X	X	X	X	X	X	X	X	X				
BLACKSTONE	drop	X	X		X	X	X	X	X	X	X	X	X	X				X	X	X	X		X	X	X	X	X
BLANDFORD	drop				X	X	X	X	X	X	X	X	X	X	X	X	X			X	X	X	X	X			
BOLTON	curb		X		X	X	X	X	X	X	X	X		X	X	X	X	X	X	X	X		X	X		X	
BOSTON	curb	X	X	X	X	X	X	X	X	X	X	X	X	X	X	X	X	X	X	X	X	X	X				X
BOURNE	drop	X	X		X	X	X	X	X	X	X			X	X	X	X	X	X	X	X	X	X	X	X	X	X
BOXBOROUGH	curb				X	X	X	X	X	X	X			X	X	X		X	X	X	X		X	X			
BOXFORD	sub		X		X	X	X	X	X	X	X			X	X	X	X	X	X	X	X		X	X	X	X	

Municipality	Collection Method	Leaves/Yard Waste	Christmas Trees	Food/kitchen scraps	Newspaper	Magazines	Junk Mail	White Paper	Cardboard	Paperboard	Phonebooks	Waxed cartons	Aseptic cartons	Clear glass	Brown Glass	Green Glass	Glass	#1 (PET) plastic	#2 (HDPE) plastic	Aluminum cans	Steel/Tin	Aerosol cans	White Goods	Scrap Metal	C&D debris	Textiles	Swap Shop
BOYLSTON	curb																										
BRAINTREE	drop	X	X		X	X	X	X	X	X	X			X	X	X	X	X	X	X	X	X	X	X		X	
BREWSTER	drop	X	X		X	X	X	X	X	X	X			X	X	X	X	X	X	X	X		X	X		X	X
BRIDGEWATER	curb	X	X		X	X	X	X	X	X	X			X	X	X	X	X	X	X	X	X	X	X		X	
BRIMFIELD	curb				X	X	X	X	X	X	X	X	X	X	X	X	X	X	X	X	X	X	X	X			
BROCKTON	drop	X	X		X	X	X	X	X	X	X	X	X	X	X	X	X	X	X	X	X	X	X	X	X	X	X
BROOKFIELD	curb	X	X		X	X	X	X	X	X	X			X	X	X	X	X	X	X	X		X	X		X	X
BROOKLINE	drop	X	X		X	X	X	X	X	X	X	X	X	X	X	X	X	X	X	X	X	X	X	X			
BUCKLAND	curb				X	X	X	X	X	X	X	X	X	X	X	X	X	X	X	X	X			X			
BURLINGTON	curb	X			X	X	X	X	X	X	X			X	X	X	X	X	X	X	X	X	X				
CAMBRIDGE	curb	X	X		X	X	X	X	X	X	X	X	X	X	X	X	X	X	X	X	X	X	X	X		X	
CANTON	drop	X	X	X	X	X	X	X	X	X	X			X	X	X	X	X	X	X	X		X	X		X	
CARLISLE	sub	X	X		X	X	X	X	X	X	X			X	X	X	X	X	X	X	X		X	X	X	X	X
CARVER	drop	X	X		X				X					X	X	X		X	X	X	X		X	X			
CHARLEMONT	sub				X	X	X	X	X	X	X	X	X	X	X	X	X	X	X	X	X						
CHARLTON	drop																										
CHATHAM	curb	X	X		X	X	X	X	X	X	X			X	X	X	X	X	X	X	X	X	X	X	X	X	X
CHELMSFORD	curb	X			X	X	X	X	X	X	X		X	X	X	X	X	X	X	X	X		X	X		X	
CHELSEA	drop	X	X		X	X		X		X	X			X	X	X	X	X	X	X	X		X				
CHESHIRE	drop	X	X		X	X	X	X	X	X	X	X	X	X	X	X	X	X	X	X	X		X	X			
CHESTER	drop				X	X	X	X	X	X	X	X	X	X	X	X	X	X	X	X	X		X	X		X	
CHESTERFIELD	curb				X	X	X	X	X	X	X	X	X	X	X	X	X	X	X	X	X	X	X	X	X	X	
CHICOPEE	drop	X	X		X	X	X	X	X	X	X		X	X	X	X	X	X	X	X	X	X	X	X			
CHILMARK	drop	X	X		X	X	X	X	X	X	X			X	X	X	X	X	X	X	X	X	X	X	X	X	X
CLARKSBURG	drop	X			X	X	X	X	X	X	X	X	X	X	X	X	X	X	X	X	X		X	X	X		
CLINTON	drop	X			X	X	X	X			X			X	X	X		X	X	X	X		X	X			
COHASSET	drop	X	X		X	X	X	X	X	X	X	X	X	X	X	X	X	X	X	X	X		X	X	X	X	X
COLRAIN	curb				X	X	X	X	X	X	X	X	X	X	X	X	X	X	X	X	X		X	X			
CONCORD	drop	X	X		X	X	X	X	X	X	X		X	X	X	X	X	X	X	X	X		X	X	X		X
CONWAY	drop				X	X	X	X	X	X	X	X	X	X	X	X	X	X	X	X	X		X	X	X	X	X
CUMMINGTON	drop				X	X	X	X	X	X	X	X	X	X	X	X	X	X	X	X	X	X	X	X	X	X	
DALTON	curb	X	X		X	X	X	X	X	X	X			X	X	X	X	X	X	X	X			X	X		
DANVERS	curb	X	X		X	X	X	X	X	X	X			X	X	X	X	X	X	X	X		X	X		X	
DARTMOUTH	curb	X	X		X	X	X	X	X	X	X			X	X	X	X	X	X	X	X		X	X		X	
DEDHAM	drop	X	X		X	X	X	X	X	X	X	X	X	X	X	X	X	X	X	X	X		X				
DEERFIELD	drop				X	X	X	X	X	X	X	X	X	X	X	X	X	X	X	X	X		X	X			
DENNIS	curb	X	X		X	X	X	X	X	X	X			X	X	X	X	X	X	X	X	X	X	X	X	X	X
DIGHTON	drop	X	X		X	X	X	X	X					X	X	X	X	X	X	X	X	X	X	X			
DOUGLAS	drop	X	X		X	X	X	X	X	X	X			X	X	X	X	X	X	X	X		X	X		X	
DOVER	curb	X	X		X	X	X	X	X	X	X			X	X	X	X	X		X	X	X		X		X	X
DRACUT	drop	X	X		X	X	X	X	X	X	X	X		X	X	X	X	X	X	X	X		X			X	
DUDLEY	drop	X	X		X	X		X	X		X			X	X	X	X	X	X	X	X		X	X	X		X
DUNSTABLE	drop				X	X	X	X	X		X			X	X	X	X	X	X	X	X		X	X			
DUXBURY	curb	X	X		X	X			X	X				X	X	X	X	X			X		X	X	X	X	X
EAST BRIDGEWATER	curb													X	X	X	X	X	X	X	X		X	X			
EAST BROOKFIELD	curb	X			X	X	X	X	X	X	X		X	X	X	X	X	X	X	X	X		X	X			
EAST LONGMEADOW	drop	X	X	X	X	X	X	X	X	X	X			X	X	X	X	X	X	X	X	X	X				

Municipality	Collection Method	Leaves/Yard Waste	Christmas Trees	Food/kitchen scraps	Newspaper	Magazines	Junk Mail	White Paper	Cardboard	Paperboard	Phonebooks	Waxed cartons	Aseptic cartons	Clear glass	Brown Glass	Green Glass	Glass	#1 (PET) plastic	#2 (HDPE) plastic	Aluminum cans	Steel/Tin	Aerosol cans	White Goods	Scrap Metal	C&D debris	Textiles	Swap Shop
EASTHAM	sub	X	X		X	X	X	X	X	X	X			X	X	X	X	X	X	X	X		X	X	X	X	X
EASTHAMPTON	drop	X	X		X	X	X	X	X	X	X			X	X	X	X	X	X	X	X		X	X			X
EASTON	drop	X			X	X	X	X	X	X	X			X	X	X		X	X	X	X		X	X			X
EDGARTOWN	drop	X	X		X	X	X	X	X	X	X			X	X	X	X	X	X	X	X	X	X	X	X	X	X
EGREMONT	curb				X	X	X	X	X	X	X	X	X	X	X	X	X	X	X	X	X		X	X	X	X	X
ERVING	drop		X		X	X	X	X	X	X	X	X	X	X	X	X	X	X	X	X	X		X	X	X		
ESSEX	curb	X	X		X	X	X		X		X			X	X	X	X	X	X	X	X		X	X		X	X
EVERETT	curb	X	X		X	X	X	X	X	X	X			X	X	X	X	X	X	X	X	X	X				
FAIRHAVEN	curb	X	X		X	X	X				X			X	X	X	X	X	X	X	X		X	X		X	
FALL RIVER	curb	X	X		X	X	X	X	X					X	X	X	X	X	X	X	X	X	X	X			
FALMOUTH	curb	X			X	X	X	X	X	X	X			X	X	X	X	X	X	X	X		X	X	X	X	X
FITCHBURG	drop	X	X		X	X	X	X	X	X	X	X	X	X	X	X	X	X	X	X	X		X	X		X	X
FLORIDA	curb	X	X		X	X	X	X	X	X	X	X	X	X	X	X	X	X	X	X	X		X	X			
FOXBOROUGH	curb	X	X		X	X	X	X	X	X	X	X	X	X	X	X		X	X	X	X		X	X			
FRAMINGHAM	curb	X	X		X	X	X	X	X	X	X	X	X	X	X	X	X	X	X	X	X		X	X		X	
FRANKLIN	drop	X	X		X	X	X	X	X	X	X	X	X	X	X	X	X	X	X	X	X	X	X	X	X	X	
FREETOWN	curb	X	X		X				X					X	X	X	X	X	X		X		X	X			X
GARDNER	drop	X	X		X	X	X	X	X	X	X	X	X	X	X	X	X	X	X	X	X	X	X	X		X	
GEORGETOWN	drop	X	X		X									X	X	X				X	X			X			
GILL	curb	X	X		X	X	X	X	X	X	X	X	X	X	X	X	X	X	X	X	X		X	X	X		
GLOUCESTER	curb	X	X		X	X	X	X	X	X	X			X	X	X	X	X	X	X	X	X	X	X	X		
GOSHEN	drop				X	X	X	X	X	X	X	X	X	X	X	X	X	X	X	X	X		X	X	X	X	
GOSLD	curb				X	X			X					X	X	X	X	X	X	X	X	X					
GRAFTON	curb	X	X		X				X					X	X	X	X	X	X	X	X	X	X	X			
GRANBY	drop	X	X	X	X	X	X	X	X	X	X	X	X	X	X	X	X	X	X	X	X	X	X	X	X	X	X
GRANVILLE	drop				X	X	X	X	X	X	X	X	X	X	X	X	X	X	X	X	X		X	X			
GREAT BARRINGTON	drop	X			X	X	X	X	X	X	X	X	X	X	X	X	X	X	X	X	X		X	X			
GREENFIELD	curb	X	X		X	X	X	X	X	X	X	X	X	X	X	X	X	X	X	X	X	X	X	X	X	X	X
GROTON	drop	X	X		X	X	X	X	X	X	X	X	X	X	X	X	X	X	X	X	X	X	X	X	X	X	
GROVELAND	curb		X		X	X	X	X	X	X	X			X	X	X	X	X	X	X	X		X				
HADLEY	drop	X	X		X	X	X	X	X	X	X	X	X	X	X	X	X	X	X	X	X		X	X	X		
HALIFAX	curb	X	X		X	X	X	X	X	X	X			X	X	X	X	X	X	X	X	X	X	X	X	X	X
HAMILTON	curb	X	X		X	X	X	X	X	X	X			X	X	X	X	X	X	X	X		X	X			
HAMPDEN	drop	X	X		X	X	X	X	X	X	X	X	X	X	X	X	X	X	X	X	X	X		X			
HANCOCK	drop		X		X	X	X	X	X	X	X	X	X	X	X	X	X	X	X	X	X	X	X	X			
HAVER	drop	X	X		X	X	X	X	X	X	X			X	X	X	X	X	X	X	X		X	X	X	X	X
HANSON	drop	X			X								X	X	X	X		X	X	X	X		X	X		X	X
HARDWICK	drop				X	X	X	X	X	X	X			X	X	X	X	X	X	X	X	X	X			X	X
HARVARD	drop	X			X	X	X	X	X		X			X	X	X		X	X	X	X	X	X	X	X		
HARWICH	drop	X	X		X	X	X	X	X		X			X	X	X	X	X	X	X	X	X	X	X	X	X	X
HATFIELD	drop	X	X		X	X	X	X	X	X	X	X	X	X	X	X	X	X	X	X	X	X	X	X	X	X	
HAVERHILL	curb	X	X		X	X	X	X	X	X	X	X	X	X	X	X		X	X	X	X		X	X			
HAWLEY	drop	X	X		X	X	X	X	X	X	X	X	X	X	X	X	X	X	X	X	X		X	X	X	X	X
HEATH	drop				X	X	X	X	X	X	X	X	X	X	X	X	X	X	X	X	X		X	X			
HINGHAM	drop	X	X		X	X	X	X	X	X	X			X	X	X	X	X	X	X	X	X	X	X	X	X	X
HINSDALE	drop	X	X		X	X	X	X	X	X	X	X	X	X	X	X	X	X	X	X	X		X	X	X	X	X
HOLBROOK	curb	X	X	X	X	X	X	X	X	X	X	X	X	X	X	X	X	X	X	X	X	X	X	X	X		



Municipality	Collection Method	Leaves/Yard Waste	Christmas Trees	Food/kitchen scraps	Newspaper	Magazines	Junk Mail	White Paper	Cardboard	Paperboard	Phonebooks	Waxed cartons	Aseptic cartons	Clear glass	Brown Glass	Green Glass	Glass	#1 (PET) plastic	#2 (HDPE) plastic	Aluminum cans	Steel/Tin	Aerosol cans	White Goods	Scrap Metal	C&D debris	Textiles	Swap Shop
HOLDEN	curb	X			X	X	X							X	X	X		X	X	X	X		X	X			
HOLLAND	sub	X																									
HOLLISTON	curb	X	X		X	X	X	X	X	X	X			X	X	X	X	X	X	X	X		X	X			
HOLYOKE	curb	X	X		X	X	X	X	X	X	X		X	X	X	X	X	X	X	X	X		X	X			
HOPEDALE	curb	X	X		X	X	X	X	X	X	X	X	X	X	X	X	X	X	X	X	X	X	X	X	X	X	X
HOPKINTON	curb	X	X		X	X	X	X	X	X	X			X	X	X	X	X	X	X	X		X	X		X	
HUBBARDSTON	drop		X		X	X	X	X	X	X	X	X	X	X	X	X	X	X	X	X	X		X	X		X	
HUDSON	drop	X	X		X	X	X	X	X	X	X	X	X	X	X	X	X	X	X	X	X	X	X	X	X	X	X
HULL	drop		X		X	X	X	X	X	X	X	X		X	X	X	X	X	X	X	X		X	X			
HUNTINGTON	drop				X	X	X	X	X	X	X	X	X	X	X	X	X	X	X	X	X		X	X	X	X	
IPSWICH	curb	X	X		X	X	X	X	X	X	X			X	X	X	X	X	X	X	X						
KINGSTON	drop	X	X		X	X	X	X	X	X	X			X	X	X	X	X	X	X	X		X	X	X	X	
LAKEVILLE	drop	X	X		X	X			X	X	X			X	X	X	X	X	X	X	X		X	X	X	X	
LANCASTER	drop	X	X		X	X	X	X	X	X	X			X	X	X	X	X	X	X	X		X	X		X	X
LANESBOROUGH	drop				X	X	X	X	X	X	X	X	X	X	X	X	X	X	X	X	X					X	X
LAWRENCE	curb	X	X		X	X	X	X	X	X	X	X	X	X	X	X	X	X	X	X	X		X	X			
LEE	curb		X		X	X	X	X	X	X	X	X	X	X	X	X	X	X	X	X	X						
LEICESTER	drop	X			X	X	X	X	X		X			X	X	X		X	X	X	X	X	X	X			
LEX	sub	X	X		X	X	X	X	X	X	X	X		X	X	X	X	X	X	X	X	X	X	X	X	X	
LEOMINSTER	curb	X	X		X	X	X	X	X	X	X			X	X	X	X	X	X	X	X		X	X			
LEVERETT	drop				X	X	X	X	X	X	X		X	X	X	X	X	X	X	X	X	X	X	X	X	X	X
LEXINGTON	curb	X	X		X	X	X	X	X	X	X	X	X	X	X	X	X	X	X	X	X		X	X		X	
LEYDEN	drop				X	X	X	X	X	X	X	X	X	X	X	X	X	X	X	X	X						
LINCOLN	drop	X	X		X	X	X	X	X	X	X			X	X	X	X	X	X	X	X		X	X			X
LITTLETON	drop	X	X		X	X	X	X	X	X	X			X	X	X	X	X	X	X	X		X	X		X	X
LONGMEADOW	curb	X	X		X	X	X	X	X	X	X		X	X	X	X	X	X	X	X	X	X	X	X		X	X
LOWELL	curb	X	X		X	X	X	X	X	X	X	X		X	X	X	X	X	X	X	X	X	X			X	
LUDLOW	curb	X	X		X	X	X	X	X	X	X	X	X	X	X	X	X			X	X	X	X	X			
LUNENBURG	curb	X	X		X	X	X	X	X	X	X	X		X	X	X	X	X	X	X	X	X					
LYNN	curb	X	X		X	X	X	X	X	X	X			X	X	X	X	X	X	X	X						
LYNNFIELD	curb	X	X		X	X	X	X	X	X	X	X	X	X	X	X	X	X	X	X	X	X	X	X	X	X	
MALDEN	curb	X			X	X	X	X	X	X	X			X	X	X	X	X	X	X	X		X				
MANCHESTER	curb	X	X		X	X	X	X	X		X		X	X	X	X	X	X	X	X	X		X	X			
MANSFIELD	curb	X	X		X	X	X	X	X	X	X			X	X	X	X	X	X	X	X	X	X	X		X	
MARBLEHEAD	curb	X	X		X	X	X	X	X	X	X			X	X	X	X	X	X	X	X		X	X		X	X
MARION	curb	X	X		X	X	X	X	X	X	X			X	X	X	X	X	X	X	X		X	X			
MARLBOROUGH	curb	X	X		X	X	X	X	X	X	X			X	X	X	X	X	X	X	X		X		X	X	
MARSHFIELD	curb	X	X	X	X	X	X	X	X	X	X	X	X	X	X	X	X	X	X	X	X	X	X	X	X	X	X
MASHPEE	drop	X	X		X	X	X	X	X	X	X			X	X	X	X	X	X	X	X		X	X		X	
MATTAPOISETT	curb	X	X		X			X						X	X	X	X	X	X	X	X		X	X		X	X
MAYNARD	curb	X	X		X	X	X	X	X	X	X	X		X	X	X	X	X	X	X	X	X	X	X	X		
MEDFIELD	drop	X	X		X	X	X	X	X		X			X	X	X		X	X	X	X		X	X			X
MEDFORD	curb	X	X		X	X	X	X	X		X		X	X	X	X	X	X	X	X	X		X	X			
MEDWAY	curb				X	X	X	X	X	X	X	X	X	X	X	X	X	X	X	X	X		X	X			
MELROSE	curb	X	X		X	X		X	X		X			X	X	X		X	X	X	X		X	X		X	
MENDON	curb				X	X	X	X	X	X	X			X	X	X	X	X	X	X	X		X	X			
MERRIMAC	curb	X	X		X	X	X	X	X	X	X			X	X	X	X	X	X	X	X						
METHUEN	curb	X	X		X	X	X	X	X	X	X	X		X	X	X	X	X	X	X	X		X	X	X	X	


Municipality	Collection Method	Leaves/Yard Waste	Christmas Trees	Food/kitchen scraps	Newspaper	Magazines	Junk Mail	White Paper	Cardboard	Paperboard	Phonebooks	Waxed cartons	Aseptic cartons	Clear glass	Brown Glass	Green Glass	Glass	#1 (PET) plastic	#2 (HDPE) plastic	Aluminum cans	Steel/Tin	Aerosol cans	White Goods	Scrap Metal	C&D debris	Textiles	Swap Shop
MIDDLEBOROUGH	curb	X	X		X	X		X	X					X	X	X	X	X	X	X	X		X	X	X		
MIDDLEFIELD	drop				X	X	X	X	X	X	X	X	X	X	X	X	X	X	X	X	X		X	X	X	X	
MIDDLETON	drop	X	X		X	X	X	X	X	X	X			X	X	X	X	X	X	X	X		X	X			X
MILFORD	curb	X	X		X	X		X	X	X	X	X	X	X	X	X	X	X	X	X	X		X	X	X	X	
MILLBURY	drop	X	X	X	X	X	X		X		X			X	X	X	X	X	X	X	X		X	X		X	
MILLIS	drop	X	X		X	X	X	X	X	X	X			X	X	X	X			X	X	X	X	X			X
MILLVILLE	curb				X			X	X	X				X	X	X	X	X	X	X	X						
MILTON	curb	X	X		X	X	X	X	X	X	X	X	X	X	X	X	X	X	X	X	X	X	X	X			
MONROE	curb	X	X		X	X	X	X	X	X	X			X	X	X	X	X	X	X	X						
MONSON	curb				X	X	X	X	X	X	X	X	X	X	X	X	X	X	X	X	X	X	X	X			
MONTAGUE	curb	X	X		X	X	X	X	X	X	X	X	X	X	X	X	X	X	X	X	X		X	X	X		
MONTEREY	drop				X	X	X	X	X	X	X	X	X	X	X	X	X	X	X	X	X	X	X	X	X	X	X
MONTGOMERY	curb				X	X	X	X	X	X	X	X	X	X	X	X	X	X	X	X	X	X					
MOUNT WASHINGTON	drop				X	X	X	X	X	X	X	X	X	X	X	X	X	X	X	X	X			X			
NAHANT	curb	X	X		X	X	X	X	X	X	X			X	X	X	X	X	X	X	X		X	X			
NANTUCKET	drop	X	X	X	X	X	X	X	X	X	X			X	X	X	X	X	X	X	X	X	X	X	X	X	X
NATICK	curb	X	X		X	X	X	X	X	X	X	X	X	X	X	X	X	X	X	X	X		X	X			
NEEDHAM	drop	X	X		X	X	X	X	X	X	X	X	X	X	X	X	X	X	X	X	X		X	X	X	X	X
NEW ASHFORD	drop	X	X		X	X	X	X	X	X	X	X	X	X	X	X	X	X	X	X	X		X	X			X
NEW BEDFORD	curb	X	X		X	X	X	X	X	X	X			X	X	X	X	X	X	X	X		X	X		X	
NEW BRAINTREE	drop				X	X	X	X	X	X	X			X	X	X		X	X	X	X	X	X	X		X	X
NEW MARLBOROUGH	drop				X	X	X	X	X		X			X	X	X	X	X	X	X	X	X		X	X		
NEW SALEM	drop				X	X	X	X	X	X	X	X	X	X	X	X	X	X	X	X	X		X	X	X		
NEWBURY	sub				X	X	X	X	X	X	X			X	X	X	X	X	X	X	X		X	X		X	
NEWBURYPORT	curb	X	X		X	X	X	X	X	X	X			X	X	X	X	X	X	X	X						
NEWTON	curb	X	X		X	X	X	X	X	X	X	X	X	X	X	X	X	X	X	X	X	X	X	X		X	X
NORFOLK	drop	X	X		X	X	X	X	X	X	X			X	X	X	X	X	X	X	X	X	X	X	X	X	X
NORTH ADAMS	drop	X	X		X	X	X	X	X	X	X			X	X	X	X	X	X	X	X	X	X	X			
NORTH ANDOVER	curb	X	X		X	X	X	X	X	X	X			X	X	X	X	X	X	X	X		X			X	
NORTH ATTLEBOROUGH	curb	X			X	X	X	X	X		X			X	X	X		X	X	X	X		X	X			
NORTH BROOKFIELD	drop	X	X		X	X	X	X	X	X	X			X	X	X	X	X	X	X	X	X	X	X	X	X	X
NORTH READING	curb	X			X	X	X		X		X			X	X	X	X	X	X	X	X						
NORTHAMPTON	drop	X	X		X	X	X	X	X	X	X	X	X	X	X	X	X	X	X	X	X		X	X	X	X	X
NORTHBOROUGH	curb	X	X		X	X	X	X	X	X	X			X	X	X	X	X	X	X	X						
NORTHBRIDGE	sub	X	X																								
NORTHFIELD	drop	X	X		X	X	X	X	X	X	X	X	X	X	X	X	X	X	X	X	X		X	X			
NORTON	sub	X																						X			
NORWELL	curb	X			X	X	X	X	X	X	X	X	X	X	X	X	X	X	X	X	X		X	X			X
NORWOOD	curb	X	X		X	X	X	X	X	X	X	X	X	X	X	X	X	X	X	X	X	X	X	X		X	X
OAK BLUFFS	drop	X	X		X	X			X		X			X	X	X	X	X	X	X							
OAKHAM	drop				X	X	X	X	X	X	X			X	X	X		X	X	X	X	X	X	X	X	X	
ORANGE	drop	X	X		X	X	X	X	X	X	X	X	X	X	X	X	X	X	X	X	X		X	X	X	X	
ORLEANS	drop	X			X	X			X		X			X	X	X		X	X	X	X		X	X			
OTIS	drop	X	X		X	X	X	X	X	X	X	X	X	X	X	X	X	X	X	X	X		X	X	X	X	X
OXFORD	sub	X	X		X	X			X					X	X	X	X	X	X				X	X		X	

Municipality	Collection Method	Leaves/Yard Waste	Christmas Trees	Food/kitchen scraps	Newspaper	Magazines	Junk Mail	White Paper	Cardboard	Paperboard	Phonebooks	Waxed cartons	Aseptic cartons	Clear glass	Brown Glass	Green Glass	Glass	#1 (PET) plastic	#2 (HDPE) plastic	Aluminum cans	Steel/Tin	Aerosol cans	White Goods	Scrap Metal	C&D debris	Textiles	Swap Shop
PALMER	drop	X	X		X	X	X	X	X	X	X			X					X	X							
PAXTON	curb	X	X		X	X	X	X	X	X	X		X	X	X	X		X	X	X	X		X	X	X	X	X
PEABODY	curb	X			X	X		X						X	X	X	X			X	X		X	X			
PELHAM	drop				X	X	X	X	X	X	X			X	X	X	X	X	X	X	X						
PEMBROKE	drop	X			X	X	X	X	X		X			X	X	X	X	X	X	X	X		X	X		X	X
PEPPERELL	drop		X		X			X	X		X			X	X	X	X	X	X	X	X		X	X	X	X	
PERU	drop				X	X	X	X	X	X	X	X		X	X	X	X	X	X								
PETERSHAM	drop				X	X	X	X	X	X	X			X	X	X	X	X	X	X	X		X	X			
PHILLIPSTON	drop	X			X	X	X	X	X		X		X	X	X	X		X	X	X	X		X	X			
PITTSFIELD	curb	X			X	X	X	X	X	X	X	X	X	X	X	X	X	X	X	X	X	X	X	X	X		
PLAINFIELD	drop				X	X	X	X	X	X	X	X	X	X	X	X	X	X	X	X	X		X	X	X	X	
PLAINVILLE	curb	X	X		X	X	X	X	X	X	X			X	X	X	X	X	X	X	X		X	X			
PLYMOUTH	drop	X	X		X	X	X	X	X	X	X			X	X	X	X	X	X	X	X	X	X	X		X	
PLYMPTON	drop		X		X	X	X	X	X			X		X	X	X	X	X	X	X			X	X			
PRINCETON	sub																						X	X			
PROVINCETOWN	curb	X	X		X	X	X	X	X		X			X	X	X	X	X	X	X	X		X	X			X
QUINCY	curb	X	X		X	X	X	X	X	X	X	X		X	X	X	X	X	X	X	X		X				
RANDOLPH	curb	X			X	X		X	X	X	X			X	X	X	X	X	X	X	X		X				
RAYNHAM	drop	X	X		X	X	X	X	X	X	X			X	X	X	X	X	X	X	X		X	X	X		
READING	curb	X	X		X	X	X	X	X	X	X			X	X	X	X	X	X	X	X		X	X			
REHOBOTH	drop	X	X		X			X	X					X	X	X		X	X	X	X	X	X	X		X	X
REVERE	curb	X	X		X	X	X	X	X	X	X			X	X	X	X	X	X	X	X		X	X			
RICHMOND	curb				X	X	X	X	X	X	X			X	X	X	X	X	X	X	X		X	X			
ROCHESTER	curb	X	X		X	X	X	X	X	X				X	X	X	X	X	X	X	X					X	
ROCKLAND	curb	X	X		X	X	X	X	X	X	X			X	X	X	X	X	X	X	X		X	X	X	X	
ROCKPORT	drop	X	X		X	X	X	X	X	X	X	X	X	X	X	X	X	X	X	X	X	X	X	X	X		X
ROWE	drop				X	X	X	X	X	X	X	X	X	X	X	X	X	X	X	X	X		X	X	X		
ROWLEY	drop				X	X	X	X	X	X	X			X	X	X		X	X	X	X		X	X			
ROYALSTON	drop				X	X	X	X	X	X	X	X	X	X	X	X	X	X	X	X	X		X	X	X	X	X
RUSSELL	drop	X	X		X	X	X	X	X	X	X	X	X	X	X	X	X	X	X	X	X	X	X	X			
RUTLAND	drop	X			X	X																	X	X			
SALEM	curb	X	X		X	X	X	X	X	X	X							X	X	X	X		X				
SALISBURY	drop	X	X		X	X	X	X			X			X	X	X	X	X	X	X	X						
SANDISFIELD	drop				X	X	X	X	X	X	X	X	X	X	X	X	X	X	X	X	X	X	X	X	X		
SANDWICH	drop	X	X		X	X	X	X	X	X	X			X	X	X	X	X	X	X	X		X	X		X	
SAUGUS	curb	X			X	X	X	X	X	X	X	X	X	X	X	X	X	X	X	X	X	X	X				
SAVOY	drop				X	X	X	X	X	X	X	X	X	X	X	X	X	X	X	X	X						
SCITUATE	drop	X	X		X	X	X	X	X	X	X		X	X	X	X	X	X	X	X	X	X	X	X	X		X
SEEKONK	curb	X	X		X	X	X	X	X	X	X			X	X	X	X	X	X	X	X	X	X			X	
SHARON	curb	X	X		X	X	X	X	X	X	X			X	X	X	X	X	X	X	X	X	X	X			
SHEFFIELD	drop				X	X	X	X	X	X	X		X	X	X	X	X	X	X	X	X		X	X		X	X
SHELBURNE	drop				X	X	X	X	X	X	X	X	X	X	X	X	X	X	X	X	X		X	X	X		
SHERBORN	drop				X	X	X	X	X	X	X	X		X	X	X	X	X	X	X	X	X	X	X		X	X
SHIRLEY	drop	X			X	X	X	X	X	X	X			X	X	X	X	X	X	X	X						
SHREWSBURY	curb	X			X	X	X	X	X	X	X	X	X	X	X	X	X	X	X	X	X	X					
SHUTESBURY	curb				X	X	X	X	X	X	X	X		X	X	X	X	X	X	X	X		X	X			
SOMERSET	curb	X	X		X	X	X	X	X	X		X	X	X	X	X	X	X	X	X	X	X	X	X	X	X	X
SOMERVILLE	curb	X	X		X	X	X	X	X	X	X	X	X	X	X	X	X	X	X	X	X	X	X	X			

Municipality	Collection Method	Leaves/Yard Waste	Christmas Trees	Food/kitchen scraps	Newspaper	Magazines	Junk Mail	White Paper	Cardboard	Paperboard	Phonebooks	Waxed cartons	Aseptic cartons	Clear glass	Brown Glass	Green Glass	Glass	#1 (PET) plastic	#2 (HDPE) plastic	Aluminum cans	Steel/Tin	Aerosol cans	White Goods	Scrap Metal	C&D debris	Textiles	Swap Shop
SOUTH HADLEY	curb	X	X		X	X	X	X	X	X	X	X	X	X	X	X	X	X	X	X	X		X	X	X	X	X
SOUTHAMPTON	drop	X	X	X	X	X	X	X	X	X	X	X	X	X	X	X	X	X	X	X	X	X	X	X	X	X	
SOUTHBOROUGH	drop	X	X		X	X	X	X	X	X	X			X	X	X	X	X	X	X	X	X	X	X		X	X
SOUTHBRIDGE	curb	X	X	X	X	X	X	X	X	X	X			X	X	X	X	X	X	X	X		X	X	X		
SOUTHWICK	drop	X	X		X	X	X	X	X		X	X		X	X	X	X	X	X	X	X	X	X	X			
SPENCER	drop	X	X		X	X	X	X	X	X	X			X	X	X	X	X	X	X	X		X	X	X	X	X
SPRINGFIELD	curb	X	X		X	X	X	X	X	X	X			X	X	X	X	X	X	X	X	X	X	X			
STERLING	curb	X	X		X	X	X	X	X	X	X	X	X	X	X	X	X	X	X	X	X		X	X		X	X
STOCKBRIDGE	drop				X	X	X	X	X	X	X	X		X	X	X	X	X	X	X	X		X	X			X
STONEHAM	curb	X	X		X	X	X	X	X	X	X	X	X	X	X	X	X	X	X	X	X	X	X	X		X	
STOUGHTON	curb	X	X		X									X	X	X		X	X	X	X		X	X		X	
STOW	sub				X	X	X	X	X	X	X			X	X	X	X	X	X	X	X		X	X			
STURBRIDGE	drop	X	X		X	X	X	X	X	X	X	X		X	X	X	X	X	X	X	X	X	X	X	X	X	X
SUDBURY	drop	X	X		X	X	X	X	X	X	X			X	X	X	X	X	X	X	X		X	X		X	X
SUNDERLAND	curb	X	X		X	X	X	X	X	X	X	X	X	X	X	X	X	X	X	X	X		X	X	X		
SUTTON	drop	X	X		X	X		X	X		X			X	X	X	X	X	X	X	X		X	X			X
SWAMPSCOTT	curb	X	X		X	X	X	X	X	X	X	X	X	X	X	X	X	X	X	X	X	X	X	X			
SWANSEA	curb	X	X		X	X		X	X					X	X	X	X	X	X	X	X		X	X			
TAUNTON	curb	X	X		X	X	X	X	X	X	X	X	X	X	X	X	X	X	X	X	X	X	X	X		X	X
TEMPLETON	sub	X	X																								
TEWKSBURY	curb	X	X		X	X	X	X	X	X	X			X	X	X	X			X	X		X	X	X		
TISBURY	curb	X	X		X	X			X		X			X	X	X	X	X	X	X	X		X	X		X	
TOLLAND	drop				X	X	X	X	X	X			X	X	X	X	X	X	X	X	X						
TOPSFIELD	curb	X	X		X	X	X	X	X	X	X			X	X	X	X	X	X	X	X		X	X			
TOWNSEND	curb	X	X		X	X	X	X	X	X	X			X	X	X	X	X	X	X	X		X	X		X	
TRURO	drop	X	X		X	X	X	X	X	X	X			X	X	X	X	X	X	X	X	X	X	X		X	X
TYNGSBOROUGH	curb	X			X	X	X	X	X	X	X			X	X	X	X	X	X	X	X	X	X	X			
TYRINGHAM	drop				X	X	X	X	X	X	X	X	X	X	X	X	X	X	X	X	X		X	X			X
UPTON	curb	X	X		X	X	X	X	X	X	X	X	X	X	X	X	X	X	X	X	X		X	X		X	
UXBRIDGE	sub	X						X																			
WAKEFIELD	curb	X	X		X	X	X	X	X		X			X	X	X	X	X	X	X	X		X				
WALES	drop	X	X		X	X	X	X	X	X	X			X	X	X	X	X	X	X	X		X	X		X	
WALPOLE	curb	X	X		X	X	X	X	X	X	X	X	X	X	X	X	X	X	X	X	X	X				X	
WALTHAM	curb	X	X		X	X	X	X	X	X	X	X	X	X	X	X	X	X	X	X	X		X				
WARE	sub																										
WAREHAM	curb				X	X		X	X	X	X			X	X	X	X	X	X	X	X		X				
WARREN	drop	X	X		X	X	X	X	X	X	X			X	X	X		X	X	X	X		X	X		X	
WARWICK	drop				X	X	X	X	X	X	X	X	X	X	X	X	X	X	X	X	X		X	X	X		
WASHINGTON	drop				X	X	X	X	X	X	X	X	X	X	X	X	X	X	X	X	X		X	X		X	
WATERTOWN	curb	X	X		X	X		X	X		X			X	X	X	X	X	X	X	X		X	X	X	X	
WAYLAND	drop	X	X		X	X	X	X	X	X	X	X	X	X	X	X	X	X	X	X	X	X	X	X	X	X	X
WEBSTER	drop	X	X		X	X	X	X	X		X	X		X	X	X	X	X	X	X	X	X	X	X		X	X
WELLESLEY	drop	X	X		X	X	X	X	X	X	X			X	X	X	X	X	X	X	X	X	X	X	X	X	X
WELLFLEET	drop	X	X		X			X	X	X				X	X	X	X	X	X	X	X	X	X	X	X	X	X
WENDELL	drop				X	X	X	X	X	X	X	X	X	X	X	X	X	X	X	X	X		X	X	X		X
WENHAM	curb	X			X									X	X	X	X	X	X	X	X		X	X			
WEST BOYLSTON	curb	X	X		X	X	X	X	X	X	X	X	X	X	X	X	X	X	X	X	X						



# Integrated Solid Waste Management System: Disposal Facilities (2003)




## Legend

### Landfills

- ◆ less than 10,000 tons per year (TPY)
- 10,000 - 49,999 TPY
- 50,000 - 124,999 TPY
- 125,000 - 199,999 TPY
- 200,000 - 475,000 TPY

### Combustion Facilities

- less than 125,000 tons per year (TPY)
- 125,000 - 449,999 TPY
- 450,000 - 749,999 TPY
- 750,000 - 1,000,000 TPY
- Community Boundary
- DEP Regional Boundary



0 5 10 20 30 40 Miles

## Data Sources


LANDFILLS AND COMBUSTION FACILITIES - DEP Bureau of Waste Prevention, Solid Waste Facility Database. Sources include: newspaper, parcel maps, estimated extent of waste compiled into USGS topographic. Digitized using USGS logo as digital orthophoto base, 1:25,000, June 2002. Tonnage information from DEP SWMP Solid Waste Database, May 2003.

MUNICIPAL BOUNDARIES - ECOMassGIS. Boundaries digitized from 1:25,000 USGS quadrangle maps.

DEP REGIONAL BOUNDARIES - ECOMassGIS. Based on municipal boundaries described above.

G:\projects\solidwaste\Map\_Fig\_04a.mxd 10/1/2003

# Active Transfer Stations & Processing Facilities: 2004



## DATA SOURCES:

TRANSFER STATIONS & PROCESSING FACILITIES - DEP Bureau of Waste Prevention, Solid Waste Facility Database. Sources include: local maps, parcel maps, estimated extent of waste compiled onto USGS topographic maps. Digitized using USGS's topographic maps, 1:25,000, June 2002. The list of 300 transfer stations and processing facilities is based on local addresses matching. Tonnage information from DEP SWP Solid Waste Database, May 2005. Permitted Processing Facilities include Municipal Solid Waste and/or Construction and Demolition Debris processing facilities.

MUNICIPAL BOUNDARIES - EOCENMapGIS. Boundaries digitized from 1:25,000 USGS quadrangle maps.

DEP REGIONAL BOUNDARIES - EOCENMapGIS. Based on municipal boundaries described above.

NOTE: Map displays permitted tons per day (TPD) where available. Reported tonnage was used when permitted tonnage was not available.

